


Control System for Super KEKB

KEKB Controls Group
Tadahiko Katoh

Present System

- EPICS based
- UNIX Server Workstations
 - abco1(KEKB) + abco2(PF-AR)
- Combined with PF-AR Control System
 - 94(KEKB) + 10(PF-AR) IOCs
- Network
 - FDDI Switched Network
 - 10 Base/T, 100 Base/TX Ethernet
- Fieldbuses
 - CAMAC Serial Highway
 - ARCNET for Power Supplies
 - Partially PLCs

System Configuration



Upgrade for Super KEKB

- EPICS System is Scalable
- Server Workstation Upgrade
- Network Upgrade
 - Switched FDDI to Gigabit Ethernet
 - Optical Fiber Cables have Already been Placed
- Additional IOCs and CPU Upgrade
 - ~ 30 Additional IOCs
- Fieldbuses
 - CAMAC or/and PLCs

Changes in Quantity

- RF Control
 - About twice
- Vacuum Control
 - Additional Fraction
- Beam Monitors
 - Additional Amount
- Data to be taken
 - Several Times More than Present
 - Increase of Network Traffic

Changes in Quality

- Control Interface for RF
 - CAMAC to PLCs Conversion
 - More Expensive but Simpler
 - CAMAC and PLCs Mixed
 - Less Expensive but More Complicated
- Hardness of Producing CAMAC Modules Again
 - We have to Design from the Scratch

Works to be Done

- More Accurate Estimation needed
- Model System using PLCs

Schedule

- 2002 RF Model System Design
- 2003-4 RF Model System Setup
- 2004 1st Server Upgrade
 - Network Upgrade
- 2006-7 Construction
- 2007 2nd Server Upgrade