


Injector Linac Upgrade for SuperKEKB overview

Kamitani Takuya

KEKB Injector

KEKB Injector Linac



The layout is optimized for 8-GeV e⁻/3.5-GeV e⁺.


e⁻ to HER : 8 GeV ~ (Primary e⁻ : 4 GeV) + (e⁺ to LER : 3.5 GeV)

e⁻/e⁺ /(PF/AR) injection modes are switched by,
 retracting/inserting the target from/to the beamline, switching the gun,
 changing the parameters (magnet strengths, acceleration phases etc).

The switching takes 45 ~ 120 sec.

Typical operation status (1)

(Periodic Injection Mode)



- 18~20 injections/day
8 min. for routine refill
23 min. after beam abort

- Injection rate
5 mA/s for e⁻ 50 Hz
(1 nC x 1 bunch)
3 mA/s for e⁺ 50 Hz
(0.6 nC x 2 bunches)

- Belle DAQ* stops during injection

- Lumi. effic.** ~ 66 %


(*) DAQ = data acquisition

(**) Luminosity efficiency =

integrated lumi./(peak lumi. x operation time)

Typical operation status (2)

(Continuous Injection Mode)



- Injecting always
 - e^+ every 20 min. (target bellows)
 - e^- quasi-continuous

- Injection rate

1.0 mA/s for e^- 10 Hz
0.5 mA/s for e^+ 10 Hz

- Belle DAQ continues with short dead time 3.7 ms after each beam pulse
(The less beam rep. rate, the smaller dead time.)


- Lumi effic. \sim 81 %
(\sim 84 % on Feb.15)

CIM improves the efficiency more than 15 %

Upgrade Requirements

-
- (1) **KEKB** **SuperKEKB**
- | | | | |
|-----------------------|---------|--------|-------------------|
| Beam Energy (e^-) | 8.0 GeV | -----> | 3.5 GeV |
| (e^+) | 3.5 GeV | -----> | 8.0 GeV !! |
- > C-band accelerator modules
-
- (2) **KEKB** **SuperKEKB**
- | | | | |
|--------------------------|-------|----------------|-----------------|
| Stored current (e^-) | 1.1 A | -----> | 9.4 A !! |
| (e^+) | 1.5 A | --> 2.6 A ---> | 4.1 A ! |
- > e^- : increase beam charge
-> e^+ : flux concentrator (e^+ capture effic.)
-
- (3) **Smaller e^+ emittance** to fit for IR & C-band module apertures
-> e^+ damping ring
-
- (4) **Faster e^+/e^- mode-switching** for Continuous e^+/e^- Injection
-> separated e^+/e^- beam lines
-> non-destructive beam monitoring


Upgrade Scheme



- e^+ energy is boosted by the C-band accelerator modules.
- e^+/e^- injections are switched by the kicker before the target, e^+ and e^- go through independent beam lines.
- e^+ emittance is reduced with the damping ring.
- both the 2 bunches are used for e^+ or e^- . (Not for e^+ and e^-)

Energy Upgrade

- e⁺ energy gain at KEKB
 - max 4.8 GeV = 21 MV/m (S-band module) x 231 m




e⁺ energy is boosted by
C-band accelerator modules.

- e⁺ energy gain at SuperKEKB
 - 8.0 GeV ~ 21 MV/m (S-band modules) x 46 m
 - + 42 MV/m (C-band modules) x 185 m

Linac Accelerator module


(From S-band To C-band)

Present S-band accelerator module



Accel. field gradient = 21 MV/m


New C-band accelerator module



Accel. field gradient = 42 MV/m

C-band Test Stand

for High power test & RF processing
of the components




C-band rf source installed in KEKB linac (2003 September)

10



C-band accel. section installed in KEKB linac (2003 September)

11



C-band R & D items

- Klystron -> Toshiba E3746, High Power Test OK
- Modulator -> compact (1/3 size), OK except inverter P.S. trouble
- Low power RF -> sub-booster OK, solid-state amp.?
- RF pulse compressor -> HPT in July 2004
- Accelerating section -> 1st prototype 41 MV/m,
breakdown at input coupler
2nd prototype HPT in July 2004
- Other RF components

– RF window	HPT OK
– Dummy load	HPT OK
– 3-dB hybrid power divider	HPT OK
– Wave guide flange	HPT OK
– RF gate valve	under consideration

Intensity upgrade

Intensity upgrade is essential for higher luminosity efficiency, even for the continuous injection mode.

- e^+ : 0.6 nC x 2 bunches --> 1.2 nC x 2 bunches
by replacing present 2.3 Tesla pulse coil
with 7~10 Tesla flux concentrator
in the e^+ capture section
for doubling the capture efficiency
- e^- : 1.0 nC x 1 bunch --> 2.5 nC x 2 bunches
by increasing the charge from the pre-injector
and using two bunches
With less bunch charge, e^- emittance and
energy-spread are smaller.

Other R & D items

- e^+ focusing flux concentrator
- beam kicker & e^- transport line
- non-destructive beam profile monitor
- beam position monitor for 50 Hz readout
- fast e-gun grid pulser switching
- fast RF phase switching
- e^+ Damping ring

Summary

- C-band R & D is in progress. High power test of the prototype C-band accelerator module has been performed since October 2003. **Most of the components are working well.**

(Remaining issues)

Breakdown at input coupler, inverter P.S. troubles
RF pulse compressor

- Beam instrumentation R & D is in progress. **Non-destructive profile monitor and 50 Hz readout of position monitor** are the main issues.
- Design study of the damping ring is in progress. **Preliminary design is fixed.**