

Accelerator Systems Division



PEP-II Progress and SLAC Future

John Seeman for the PEP-II Team
Particle and Particle-Astrophysics Directorate
Stanford Linear Accelerator Center

KEKB ARC Meeting
December 4, 2007



Topics

- Highlights of PEP-II Run 6.
- Main activities for Fall 2007 down
- Plan for PEP-II Run 7 in FY2008
- Shut down planning
- Brief SLAC Overview



The PEP-II Team







New Items for PEP-II in Run 6

- Advances:
 - Two new HER RF stations.
 - New skew quad fix for IR2 LER x-y coupling found and implemented. Specific luminosity is higher.
 - Fast dither IP feedback in and working (10 Hz).
 - Vertical vibration in IR support tube damped with BaBar's help.
- Problems:
 - Vacuum leak in HER IR Q4 chamber
 - Damaged coils on IR Quadrupole Q2
 - HER flex-flange seals show discharges
 - More PG&E site wide AC power dips than normal.




HER Flex flange RF seal






Example of a melted RF seal

These GlidCop fingers are brazed onto the SS mounting plate




Inside of ring






Two-gap model of a cavity





Novokhatski



New RF Seal Design: Installed 187 New Seals in Fall 2007




Same as the old design but omega fingers made out of silver plated Inconel. The entire SS plate is silver plated.






HER HOM power



Novokhatski



LER HOM power in runs



Novokhatski



RF LER current limits with new Pre-amplifiers

Operational Limits due to LOM Longitudinal Stability

Net System Damping


Combining the estimated fast modal growth rate (σ_l) with the damping due to the Longitudinal LGDW (Δ_l), the net system damping for future operation in LER can be estimated.

Assuming for operation a safety margin (SM) equal to $SM = \sigma_l$,


$$\sigma_{NET_l} = \Delta_l - \sigma_l - SM = \Delta_l - 2\sigma_l.$$

(Rivetta)

. $V_G = 4.05MV$




. $V_G = 4.5MV$






Measurement of phase transients along bunch train

LER)



Streak camera image




(Cheng)




200ns horizontal scale

Near the bunch train gap, 1722 bunches with 24 bunches gap





Beam Aborts Statistics




- Total fault rate roughly proportional to beam power
- Lots of scatter, especially for RF (processing)



Beam Aborts


- 7 classes of aborts tracked since June 21:
 - 9.7 total aborts per day
 - 2.6 RF aborts per day
- 73% -- Non-RF Aborts
 - 38% Transverse & Radiation
 - 19% Misc Non-RF
 - 8% Longitudinal
 - 8% Unknown Non-RF
- 27% -- RF Aborts
 - 20% HPRF
 - 4% LLRF
 - 2% RF Setup





IP Characterization

- Use BaBar's tracking resolution and prime venue for measuring important parameters at the IP



- Three analyses each measuring ε_y, β_y^*
 - $d\text{Lumi} / dz$ vertexing e^+e^- and $\mu^+\mu^-$ events
 - $\sigma_{y\text{Lumi}}(z)$ $\mu^+\mu^-$ events
 - $\sigma_{y'\text{Lumi}}(z)$ $\mu^+\mu^-$ events




BaBar IP measurements reported online

- Luminous Region
 - centroids $\{ x, y, z \}$
 - sizes $\{ x, z \}$
 - tilts $\{ dx/dz, dy/dz \}$
 - dL/dz fit $\{ \Sigma_z, \beta^*_y, z_w, z_c \}$every 10 minutes
every ~hour
- Boost Trajectory
 - mean $\{ x', y' \}$
 - spread $\{ x'_{HER}, y'_{HER} \}$every 10 minutes
every 30 minutes



Bunch Length Extraction from dL/dz Fits

20070531-121925




$\beta_y^* = 13\text{mm}$

$$\Delta\Sigma_z^2 = 10.3 \text{ mm}^2 \pm 0.4 \text{ mm}^2$$


$$\sigma_{z,H} = 10.9 \text{ mm} \pm 0.2 \text{ mm}$$
$$10.4 \text{ mm}$$

$$\sigma_{z,L} = 10.8 \text{ mm} \pm 0.2 \text{ mm}$$





IP Beta Function Measurements (BaBar)



PEP
phase
advance
 β_2





Accelerator Systems Division

New Skew Magnets to Improve LER Vertical Emittance

→ 10 to 50% gain at fixed currents


$$\varepsilon_{x,y} = 3.84 \cdot 10^{-13} \gamma^2 \frac{\langle H_{x,y} / |\rho^3| \rangle}{J_{x,y} \langle 1/\rho^2 \rangle}, \quad \text{where} \quad H = \beta \eta'^2 + 2\alpha \eta \eta' + \frac{1 + \alpha^2}{\beta} \eta^2.$$

Physicist design (F-J. Decker)







HER emittance on July 18 (red), 2007






LER emittance in July, 2007





Record peak specific luminosity obtained in 2007
after reducing LER coupling for lower γ emittance




Managed to get a peak specific luminosity (as shown on red) with a lower LER current.


28-aug 9:00am,
peplog




Specific Luminosity in PEP-II

•











August 2007 was our Best month

**New month
and 30 day
records**





A look at the timeline of BaBar data collection vs physics output



- There are more than 200 ongoing analyses of BaBar data.
- More than 317 papers published & submitted for publication.



PEP-II Parameter Goals have not changed!

Parameter	Units	Design	Present best	2008 goal
I+	mA	2140	2940	4000
I-	mA	750	1940	2200
Number bunches		1658	1722	1740
β_y^*	mm	15-20	10	8-8.5
Bunch length	mm	15	11-12	8.5-9
ξ_y		0.03	0.047-0.065	0.054-0.07
Luminosity	$\times 10^{33}$	3	12	20
Int lumi / day	pb^{-1}	130	911	1300

4 times design

7 times design




Fall 2007 Down Activities (September 4-December 3)

- Finished LER BPM replacement.
- Added 5 HER Arc HOM bellows.
- Added 12 LER IR2 HOM bellows.
- Replaced 187 HER Arc flex-flange RF “Omega Seals”.
- Installed two new LER Q5 chambers in IR2.
- Installed repaired HER Q4L chamber.



Interaction Region Layout


Summer 2007 shutdown work





Side view of BaBar

Q2 magnet



Section through BaBar & near IR
For information only, do not scale


Acad Eng- BabarSection2
Dwn- S.J.Metcalf
This Revision- 4/23/01




HER Q4L chamber

- Installed new, larger aperture, Al chamber during 2006 down
- Flexflange weld failed April 2007, temporary repair with Vacseal
- Removed Al chamber and reinstalled old StSt chamber while Al chamber repaired
- Flexflange replaced with fixed flange

Old StSt chamber




New Al chamber





HOM absorbing bellows Components







HOM absorbing bellows

In IR 2 we are replacing 5 bellows sections in the upstream LER and HER and 7 units in the downstream LER with bellows modules that contain HOM absorbing tiles. We hope to reduce the HOM power in this area

Novokhatski
Weathersby
Kurita
Reeck
Metcalfe

Absorbing tiles






General Overall Plan for Run 7 (Dec 2007-Sept 2008)

- Start the linac and PEP-II on December 7.
- Run through the holidays.
- Do more machine studies (MD) early to increase luminosity at the beginning of the run.
- Find the optimum luminosity condition by early spring.
- Run through September 30 with best steady state conditions.



- **PEP II Integrated Luminosity (1/fb)**





PEP-II Shut Down

- PEP-II will stop producing data for BaBar on September 30, 2008, about ten months from now.
- PEP-II and BaBar will then transition rapidly into a “Minimal Maintenance State (MMS)” which takes just over a year.
- In the medium time frame, PEP-II will be at this MMS with some effort going into tunnel maintenance, safety lighting, electrical safety and mechanical safety. Valuable items will be preserved.
- For long term, D&D of PEP-II is being studied. A DOE review was held August 6-7, 2007.




SLAC Future Options

- Ongoing programs: ILC, PEP-II, SPEAR-3, ATLAS, LARP, Astrophysics, EXO-200
- Near term projects: LCLS
- Possible future projects: LSST, SNAP, ATLAS upgrades, LCLS upgrades, PEP-LS, LHC upgrades, High Gradient program, EXO2000, Super-B, ...
- SLAC has started a long range planning exercise looking at these future projects.
Study not finished yet.



Super-B Factory Design




- SLAC is contributing modestly to the design effort for a Super-B Factory. Helped produce a Design Report in Spring 2007 (SLAC Report R-856). The goal is a factor of 100 increase in luminosity over PEP-II. Uses “ILC-like” damping rings with very small emittances, crab-waist at the IP, and smaller beam currents to save power.
- Supporting modestly the effort of INFN in Italy leading towards a Super-B accelerator and detector to be built near Rome.
- SLAC could consider contributing in-kind accelerator and detector components after September 2008 when PEP-II and BaBar are turned off. Perhaps starting in FY2011.





LCLS Progress

- Injector installed Spring 2007.
- Injector and first bunch compressor successfully tested by August 2007.
- Beam achieved 15 GeV.
- Second bunch compressor installed Fall 2007.
- New compressor will be tested January 2008.
- Downstream LCLS with undulator to be installed spring-Fall 2008 and commissioned in December 2008.
- First users in Summer 2009.
- Full set of users in Spring 2010.





PEP-II Conclusions

PEP-II accelerator in Run 6 was more difficult than planned but the run ended well.

Execution of the Fall 2007 shut down went well.

Upgrades towards $\sim 2 \times 10^{34}$ are done with the aim of 250 fb⁻¹ more to 750 fb⁻¹ total.

The luminosity will be ramped as fast as possible in Run 7.

PEP-II will integrate as much luminosity as possible.

PEP-II will turn off September 30, 2008.