

KEKB Control System

June 8, 1995

**Tadahiko Katoh
and
KEKB Controls Group**

KEKB Control System Design

- ◆ System Requirements
- ◆ Constraints
- ◆ Basic Concepts
- ◆ System Architecture

System Requirements

- ◆ Sources
- Equipment Groups
 - ◆ Magnet and Power Supply
 - ◆ RF
 - ◆ Beam Monitor
 - ◆ Vacuum
 - ◆ Beam Transport
- Operations Group
- Accelerator Physicists
- Controls Group

System Requirements

- ◆ Requirements
 - All the data that are possible to take should be taken.
 - All the data that are taken should be saved for later analyses.
 - All the operation should be recorded for later inspection.
 - All the machine parameters and information about the machine components should be stored in the database.
 - The man-machine interface should be operator-friendly.
 - The programming environment should be programmer-friendly.
 - The overall response time to an operator's request should be less than a second.

Constraints

- ◆ Reuse CAMAC as equipment interface
- ◆ Schedule
 - Control Systems Final Design
December, 1995
 - Removal of MR equipment
January, 1996
 - Start Control Systems Installation
September, 1996
 - Complete Control Systems Installation
March, 1998
 - KEKB Commissioning
December, 1998
- ◆ Man-Power
 - 12 KEKB Controls Group Members
 - 11 Linkmen from Other Groups


Basic Design Parameters

- ◆ Number of Control Points ~ 50,000
- ◆ Data Taking Rates 0.01 ~ 100 Hz
- ◆ Required Response Time ~ 1 sec.

- ◆ Number of BPMs ~ 800
- ◆ Number of Steering Magnet PSs ~1,800
- ◆ Number of B-, Q-, Sx-Magnet PSs ~ 340

System Architecture

◆ System Configuration



Standard Model Architecture

- ◆ **Presentation Layer**
 - **Operator's Consoles**
 - ◆ X Window
 - **Database Management**
 - ◆ ORACLE, SYBASE
 - **Alarm Generation/Recording**
 - **Data Logging**
 - **Data Display**
 - ◆ CATV Network
 - **Simulation**
 - ◆ SAD Program
 - **High-Speed Network**
 - ◆ FDDI, Distributed Shared-Memory Network, etc.
 - **Gateway to KEK Laboratory Network**


Standard Model Architecture

- ◆ **Equipment Control Layer**
 - **Standard Interface**
 - ◆ VME, VXI, GPIB, etc.
 - **Computers**
 - ◆ Workstation + VME
 - ◆ VMEbus Board-Computer
 - **Operating System**
 - ◆ VxWorks, Windows NT, etc.
 - **Data Input/Output Interface**
 - ◆ CAMAC, GPIB, Power Supply Interface

- ◆ **Device Interface Layer**
 - **Standard Interface**
 - ◆ CAMAC, VXI, GPIB, etc.

Input Output Computer

◆ Configuration



* under development

Basic Numbers of the Control System

- ◆ Number of Server Workstations 2
- ◆ Number of Workstations ~ 10
- ◆ Number of IOCs(VME Subracks) ~ 60
- ◆ Number of CAMAC Crates ~ 100
- ◆ Number of X-Terminals(Consoles) ~ 10
- ◆ Number of X-Terminals(Others) ~ 50

What is EPICS?

- ◆ **Experimental Physics & Industrial Control System**
 - Originated from Los Alamos National Laboratory
 - Worldwide Collaboration
 - ◆ APS at ANL
 - ◆ CEBAF
 - ◆ ALS and Gamasphere at LBL
 - ◆ STAR at BNL
 - ◆ RF Control at SLAC
 - ◆ Cryogenic System Control at DESY
 - ◆ TESLA Injector at Saclay and DESY
 - ◆ KECK Observatory in Hawaii
 - ◆ MIT Bates
 - ◆ Duke FEL at Duke University
 - ◆ GEMINI
 - ◆ Etc.

◆ Hardware supported by EPICS

- Workstations
 - ◆ Sun, HP
- IOCs
 - ◆ Microprocessors which run VxWorks
 - ◆ 680x0, Alpha, etc.
- Interfaces
 - ◆ VME
 - ◆ VXI
 - ◆ CAMAC
 - ◆ GPIB
 - ◆ PLCs
 - ◆ Allen Bradley, Siemens, etc.

◆ Software used with EPICS

● Presentation Layer


- ◆ X-Window and Motif Window
- ◆ DM/EDD(Display Manager/Display Editor)
- ◆ MEDM for designing screens
- ◆ PV-WAVE, Labview, Wingz
- ◆ NODAL
- ◆ tcI/TK
- ◆ ObjectStore(Object Oriented Database System)
- ◆ cdev(Control Device)

● IOC Layer

- ◆ DCT(Database Configuration Tool)
- ◆ GDCT(Graphical DCT)
- ◆ BURT(Backup and Restore Tool)

EPICS Architecture

◆ Functional Configuration



EPICS Architecture

◆ Functional Configuration

