

Beam Transport Line

Kikuchi M./MAC/24Jan97

1. Transport line
 - 1.1 Collimation system
 - 1.2 Design of J-Arc
 - 1.3 Magnets
 - 1.4 Beam position monitor etc.
2. Injection system
 - 2.1 Kicker magnets
 - 2.2 Septum magnets
3. Summary

1. Transport line (Fig 1,2)

Linac beam

normalized emittance	1.5e-3 (e+)	0.25e-3 (e-)
[unnormalized emittance	2.2e-7 (e+)	1.6e-8 (e-)]
energy spread	1.25e-3 (e+)	1.25e-3 (e-)

Acceptance

transverse	2.6e-6 (e+)	2.6e-6 (e-)
energy spread	5e-3 (e+)	5e-3 (e-)

Ring acceptance (worst case)

transverse	1.2e-5 (e+)	1.2e-5 (e-)
energy spread	5e-3 (e+)	5e-3 (e-)

1.1 Collimation system (Fig 1,3,4)

Energy collimation

Necessary to match the energy acceptance of the ring as well as to reduce the beam loss in the tunnel.

Two sections are prepared:

BSY3 --- up to 10% is expected. Radiation shields accept
100% loss. (cf. simulation Fig 3,4)

Entrance of Arc-1 --- up to 1% is assumed. Radiation shields
allow 1% loss.

Problem: Primary-beam scattered at the edge of collimator

Orbit of particles with energy loss ΔE and scattering angle $\Delta \theta$

$$x = R_{16} \Delta E / E + R_{12} \Delta \theta$$

R16 and R12 from BSY3 have their first maximum at downstream points which is not in the radiation-controlled area have no special shielding.

[R16 and R12 from the entrance of Arc-1 have also maximum at points in the Arc-1. Arc-1 is, however, in the radiation controlled area and there will be no problem.]

Quantitative estimation is undergoing.

Emittance collimation

Two collimators which are 90 degree apart in each plane are placed in the slope of MR-Injection tunnel (for horizontal plane) and in the Arc-4 (for vertical plane). These places are deep in the underground and there will be no radiation problem.

1.2 Design of J-Arc (Fig 5,6)

Isochronous and achromatic with momentum band width of 1.8%.
Specification of Linac beam is $\pm 1.2\%$.

1.3 Magnets

Design is completed. All magnets were ordered and in fabrication

1.4 Beam position monitor etc.

BPM (Fig 7,8,9,10)

Pick-up electrode L=15cm

Signal processing: 8 signals are combined through delay-cable.
Combined signal are recorded in the digital oscilloscope. Overall speed is 1Hz. (Fig 7)

Experiment at the AR Injection line:

Precision < 0.16 mm (Fig 8)

Demonstrate a possibility of energy feedback to

Linac. (Fig 9,10)

- Wire scanner

Four wire scanners are installed at the straight section. (Fig 1)

2. Injection System

- Beta function at the injection point (Fig 11,12,13,14)

Beta-x of injection beam to minimize the injection aperture

[beam clearance 2.5σ for injected beam

4σ for circulating beam.

damping time 40ms (e-) 80ms (e+)

Effective septum-width 6mm]

--> Beta-x = 100 m

- Physical aperture at the septum

Decided the physical aperture at the septum as

$1.2e-5$ (e-) $2e-5$ (e+) ,

corresponding to the septum position of 32mm(e-) and 43mm(e+) which are greater than aperture at the mask.

- Bump orbit

No DC-bump: use only kicker-bump in order to avoid adverse effects such as hysteresis of steering magnets, higher order dispersion and path length etc..

- Vacuum is not separated from the ring to avoid emittance increase due to multiple scattering in the window.

2.1 Septum magnets (Fig 15,16,17,18)

- Passive septum:

Full-sine 120μ sec rather than half-sine 60μ sec in order to reduce long-term leak field due to eddy current.

- Field stability of $0.5 \cdot 10^{-3}$ to decrease the injection amplitude due to septum jitter which is sizable if the field jitter is greater than $1 \cdot 10^{-3}$.

2.2 Kicker magnets (Fig 19,20,21)

Lumped circuit type

		electrons		positrons	
		one-turn	multi-turn	one-turn	multi-turn
Deflection angle	mrad	0.34	0.37	0.825	0.87
Field	G	387	418	410	430
Current	kA	1.33	1.45	1.39	1.46
Pulse width	μ sec	2.5		2.5	
Frequency	Hz	50		50	
Vacuum chamber	mm ²	120w	85h	120w	85h
Magnet length	m	0.25		0.25	
Number of magnet		4	3	4	3

Power loss in the ceramic chamber

Power loss due to eddy current ~ 100 w for 6μ m (Fig19)

Power loss due to image current (Fig 20)

-Theory on axes-symmetric ceramic pipe with inner coating.

[A. Piwinski, IEEE NS-24 No3(1977)1364]

-Heating up of ferrite was not observed.

-Experiment is larger than the theory by factor of (5~8). (Fig 21)

-Power-loss in LER is estimated from theory multiplied by (5~8)

--> 715W~1140W for 6μ m,

380W~610W for infinite thickness

Conclusion

Power loss is ~ 1 kW in total ---> water-cooling is necessary.

3. Summary

Acceptance of current design is compatible with the requirements of Linac and the rings.

Collimation system has been designed.

Proposed collimator system is able to cut the energy tail of 10%.

Emittance collimation is also possible.

Design of J-Arc has been completed. It is Achromatic and isochronous up to 1.8% and satisfies the specifications.

Strip-line BPM system was developed. Precision is less than 0.2mm.

Design of injection system.

Prototype of passive septum magnet is under construction.

Estimated power loss in the ceramic chamber amounts to 1kW.













Fig 1




TYPICAL CROSS SECTION

Fig 2

Layout of BSY3

-  Bend
-  Quad
-  H-Steer
-  V-Steer
-  BPM
-  Screen+WCM
-  Collimator
-  Acc. Structure



LINAC SY3



Fig. 2

Positrons after ECS

Acceptance ← → ECS加速





Fig 3

Bunch center
Off Crest

Longitudinal-Wake
 $Q_r = 1 \text{ nC}$


Phase Error
 $\delta\theta_{SET} = 2 \text{ deg}$

KLY HV jitter
 $\frac{\delta V}{V} = 0.15\%$


Sub BST jitter
 $\delta\theta_{SB} = 0.22 \text{ deg}$

Inject jitter
 $\delta\theta_{inj} = 1.0 \text{ deg}$


SY3 (8.0 GeV) Phase Space Plot




Energy plot



ARC (1.5 GeV) Phase Space Plot






Energy plot




Positron Line V9.124:R16 from QXF2

20:33:13 Friday 10-May-96









Layout of J-Arc

Fig 5


Emittance growth in J-arc

No. of BM : 6



uniform distribution
in momentum

Fig 6




Signal processing scheme of the single-pass BPM system

Fig 7

Wed 30/Oct/1996 19:30:34 JST

File



50 data
 標準偏差
 standard deviation
 3.15 mm

Fig. 8

196 10/29 (火) 7:10 ~ 7:30

Tue 29/Oct/1996 16:34:23 JST

F11





Fig. 9

Electron

$e^-: 2J_i(\text{micro m})$ for $\beta_R = \{40, 60, 80, 100, 120\}$ m
(RING)




β_x (inj)

Fig 11

Positron

et:2Ji(micro m) for beta={40,60,80,100,120} m
(RING)



β_x (inj)

Fig 12

Electron

inj-6.125_param(g)

Ring emittance	1.80E-08	(m)
Inj emittance	1.60E-08	(m)
Septum jitter	0.1	(%)
Rep time	100	(ms)
Damping time	40	(ms)
--- at QM5 ----		
Ring beta	89.7375	(m)
Inj beta w/o septum jitter	20	(m)
Inj beam-size w/ septum jitter(2.5 sigma)	1.86171	(mm)
w/o septum jitter(2.5 sigma)	1.41421	(mm)
Ring beam-size(4 sigma)	5.08374	(mm)
Effective septum-width	6.24326	(mm)
Injection aperture	5.14E-06	(m)
--- at the septum ---		
Ring beta	83.0356	(m)
Inj beta	9.2	(m)
Inj beam-size(2.5 sigma)	1.796	(mm)
Ring beam-size(4 sigma)	4.89022	(mm)
Effective septum-width	6	(mm)
Aperture at the septum	1.20E-05	(m)
Position at Kicker	26.676	(mm)
Angle "	-1.7283	(mrad)
Maximum amplitude of injected beam	20.669	(mm)
Septum position	31.5662	(mm)
DC-bump height	0	(mm)
" angle	0	(mrad)
Inj position	39.3622	(mm)
" angle	-2.7478	(mrad)
--- Magnet strength ---		
Kicker	0.930091	(mrad)
DC-bumper	0	(mrad)

$$\text{kicker max } \frac{32}{26.7} \times 0.93 = 1.11$$

$$\text{one-turn } \frac{39.4}{26.7} \times 0.93 = 1.37$$

Fig 13

Positron

inj+9.125_param

Ring emittance	1.80E-08	(m)
Inj emittance	2.20E-07	(m)
Septum jitter	0.1	(%)
Rep time	100	(ms)
Damping time	80	(ms)
--- at QM5FL ----		
Ring beta	102.145	(m)
Inj beta w/o septum jitter	25	(m)
Inj beam-size w/ septum jitter(2.5 sigma)	6.02147	(mm)
w/o septum jitter(2.5 sigma)	5.86302	(mm)
Ring beam-size(4 sigma)	12.1425	(mm)
Effective septum-width	6.31503	(mm)
Injection aperture	1.63E-05	(m)
--- at the septum ---		
Ring beta	92.3	(m)
Inj beta	17.1909	(m)
Inj beam-size(2.5 sigma)	5.72653	(mm)
Ring beam-size(4 sigma)	11.5425	(mm)
Effective septum-width	6	(mm)
Position at Kicker	31.4226	(mm)
Angle "	3.32048	(mrad)
Maximum amplitude of injected beam	38.8213	(mm)
Aperture at the septum	2.00E-05	(m)
Septum position	42.9651	(mm)
DC-bump height	0	(mm)
" angle	0	(mrad)
Inj position	54.6916	(mm)
" angle	6.29991	(mrad)
--- Magnet strength ---		
Kicker	1.9063	(mrad)
DC-bumper	0	(mrad)

$$\text{kicker max } \frac{43}{31.4} \times 1.906 = 2.61$$


$$\text{one-turn } \frac{54.7}{31.4} \times 1.906 = 3.32$$

Fig 14

Passive septum parameter(e-)

Deflection angle(mrad)	40
Peak magnetic field(T)	1.2
Septum thickness(mm)	1
Free aperture(mm)	$10^H \times 38^W$
Core length(m)	1
Number of turn	1
Magnet inductance(μ H)	6.1
Pulse width(μ sec)	120
Repetition(Hz)	50
Peak current(kA)	9.0
Peak voltage(kV)	3.4
Current stability(%)	0.05

Fig 15



UNITS



Length	: mm
Flux density	: T
Field strength	: A m ⁻¹
Potential	: Wb m ⁻¹
Conductivity	: S m ⁻¹
Source density	: A cm ⁻²
Power	: W
Force	: N
Energy	: J
Mass	: kg

PROBLEM DATA
 curtest-o-f-12.tr
 Quadratic elements
 XY symmetry
 Vector potential
 Magnetic fields
 Transient solution
 Time = 0.0006
 5194 elements
 10545 nodes
 9 regions

Fig 16

— By=9.5cm/By(time30 μ sec:13.2cm)
 — By=8.5cm/By(time30 μ sec:13.2cm)
 — By=5cm/By(time30 μ sec:13.2cm)

セブタムマグネット 60 μ sec 半波
1.26T(13.2cm:30 μ sec)



μ sec





Fig 17



セプタムマグネット 60 μsec 全波
 1.26T (13.2cm:30 μsec)





Fig 18

Test of the ceramic chamber
for
KEKB Kicker Magnet system

1997 Jan

KEKB Beam Transport Group

1: Power Dissipation due to Eddy Currents

Bench Test

$B = 0.675$ K Gauss

Frequency 50 Hz

Ceramic chamber coating thickness $2.5 \mu\text{m}$ $6 \mu\text{m}$

Power Loss	Test Bench	Calculation
$2.5 \mu\text{m}$ (W)	40W	65W
$6 \mu\text{m}$ (W)	60W	120W

Fig 19

2: Power Dissipation due to Image Currents


<AR large current accelerator study in 1996>

Setup

Three Kinds of ceramic Chambers are installed on AR east side straight section .

The temperature were measured at the two positions of each chamber.

Measure Temperature at two points



Coating Thickness

Chamber 1 2.5 μm

Chamber 2 4 μm ← water-cooled at fringes

Chamber 3 6 μm





Fig 21