



PEP-II Status & Plans

John Seeman

Visit to KEK
March, 1999




PEP-II Construction


The PEP-II project started construction in 1993.

The project was a three laboratory collaboration (LLNL, LBNL, and SLAC).

This collaboration was strong and worked well. It is a good model for future projects.

We also had strong support from the DOE and Congress which allowed us to finish in a timely manner and efficiently.








PEP-II Parameters

	e^+	e^-
Beam energy (GeV)	3.1	9
Beam current (A)	2.14	0.75
β_y^* (cm)	1.5	1.5
ϵ_x (ϵ_y) (nm)	49 (1.5)	49 (1.5)
σ_x (μm at IP)	157	
σ_y (μm at IP)	4.9	
σ_z (cm)	1.0	1.15
Luminosity	$3 \times 10^{33} \text{ cm}^{-2} \text{ s}^{-1}$	
Tune shift	0.03	
Beam aspect ratio (v / h at IP)	0.04	
Number of beam bunches	1658	
Bunch spacing (m)	1.26	
Beam crossing angle	0 (head-on)	

Low Energy Ring 1/2 Cell



Low Energy Ring Arc Cell Mockup at LBL






RIF Cavity Production






PEP-11-Factory

RF Cavity




PEP-B-Factory




HER Cavities
Region 12

PEP-II I.R. and BaBar Detector in IR-2



Elevation View of PEP-II I.R. and BaBar


Interaction Region




meters

IR WBS
(± 3m)

Apley, R.G.C.
M. Sullivan
Jan 21, 1995




Plan View of Near I.R. Components




- Magnets are buried inside Support Tube, inside BaBar
- Immersed in 15 kG BaBar solenoid field
- B1 is surrounded by BaBar SVT



Permanent Magnet Crew - 04/09/98




COT Magnet Support Tube Assembly






Support Cable Installation R-2



Background Detectors in IR-2, Fall 1998



PEP-II

Commissioning Overview

Our overall plan was for phased commissioning to allow staging time to fix problems.

The HER was finished in June 1997 with commissioning time in June and September, 1997, and January 1998.


The LER was finished in July 1998.

Both rings were commissioned in July , November, and December 1998 and January and February 1999. Progress has been very rapid.

First collisions were observed in July 1998, two months ahead of our collision milestone.

PEP-II was turned off February 22, 1999, to install BABAR. The PEP-II beams are scheduled to resume May 7.

A dedication ceremony with Secretary Richardson was held October 26, 1998.



Commissioning Team

J. T. Seeman
T. Himel

PEP-II Commissioning
PEP-II Run Coordinator

M. Zisman (LBNL)
U. Wienands
D. Schultz / R. Iverson
T Mattison, W Kozanecki (Saclay)
M. Sullivan

LER Commissioning
HER Commissioning
Injection Commissioning
Backgrounds
Collisions

Regular Shift Takers - 39 total

SLAC:

J. Ciendenin
S. Ecklund
A. Fisher
R. Iverson
T. Mattison
I. Reichel
M. Stanek
U. Wienands

V. Bharadwaj
F. J. Decker
R. Erickson
S. Heifets
P Krejcik
M. Minty
M. Ross
M. Sullivan
F. Zimmerman

Y. Cai
M. Donald
T. Fieguth
T. Himel
A. Kulikov
N Phinney
J. T. Seeman
J. Turner

LBNL:

S. Chattopadhyay
M. Furman
G. Portmann
M. Zisman

W. Barry
J. Corlett
D. Li
R. Rimmer

J. Byrd
W. Decking
H. Nishimura
S. Zholents

Saclay:

W. Kozanecki

CERN:

B. Zotter

A. Hofmann

M. Placidi

Systems Experts - Come in for specially scheduled activities

RF:

R. Tighe

P Corredoura

H. Schwartz

Transverse Feedback:

W. Barry

D. Li

Longitudinal FB:

D. Teytelman

J. Fox

S. Prabhakar

Backgrounds:

T. Mattison

W. Kozanecki

Background Commissioning Team

System manager: Tom Mattison

Roy Aleksan, Dave Aston, Henry Band, Jed Beach, Abdel Benabed, Steve Berridge, Tom Borak, Abdel Boucham, Dominique Boutigny, Bill Bugg, Pat Burchat, Bob Byers, Fred Catania, Chih-hsiang Cheng, Richard Cizerone, Dave Coupal, Gianni DeDomenico, Shiral Devmal, Hobey Destaebler, Sandrine Emery, Jean-Claude Faivre, Ted Fieguth, Andre Gaidot, Terry Geld, Cherie Goodenough, Fred Goozens, Joe Hargis, Adil Hasan, Carsten Hast, David Huffaker, Xinh Huynh, Jim Johnson, John Kadyk, Yannis Karyotakis, Lewis P. Keller, Roy Kerth, David Kirkby, Witold Kozanecki, Trevor Lanting, Francois LeDiberder, Vincent LePeltier, Rusty Malchow, Benjamin Mayer, Adrian McKemey, Brian Meadows, Tim Meyer, Eric Nehrlich, Ralph Nelson, Jean-Yves Nief, Jim Olsen, Patrick Petitpas, Sibylle Petrak, Mark Petree, Ed Potter, Chris Roat, Natalie Roe, Mike Ronan, Sumit Sen, Vivek Sharma, Art Snyder, Mike Sokoloff, Aron Soha, Mike Sullivan, Hiro Tanaka, Vincent Tisserand, Walter Toki, Nicolas Treps, Sophie Trincaz-Duvoid, Andrea Valassi, Sophie Versillé, Steve Wagner, Achim Weidemann, Guy Wormser, Katerina Zachariadou

*In addition, I would like to offer special thanks
to those junior members of the participating groups
who have toiled so hard to acquire and/or analyze the data!*

PEP-II

Commissioning Results

Both rings perform very well. The uptime is very good.

The control system, extended from the SLC system and EPICs, is mature and has helped a great deal in rapid commissioning.

The RF system and the feedback systems are real technical successes.

Injection is rapid with easy complex bunch patterns changes in minutes.

Top-off and filling occur in minutes for both beams.

There are a few vacuum chambers with elevated temperatures at high beam currents. These chambers will be cooled or replaced during the present down. Full current capability will be ready for both beams in May.

The vacuum pressure in the HER is great and is still scrubbing.

The vacuum pressure in LER is improving but slowly. There are a few leaks in the Arcs which keep the pressure-rise-with-current higher than we hoped for. Extensive leak checking work is underway for this down. There is a non-linear pressure rise in the LER straight sections due to, most likely, electron multipactoring which outgasses the stainless steel chambers. There is evidence that these chambers will scrub with time.

We have a good understanding of the detector backgrounds which can be traced, to a large degree, to these rising vacuum pressures. The LER pressure increases will likely dominate the backgrounds for our early data taking. This summer, we will scrub with care, find ways of increasing the luminosity at low currents, and will actively implement fixes.

PEP-II

Winter Run Highlights

- **Peak LER current = 1171 mA (lifetime ~ 25 min)**
- **Peak HER current = 507 mA (lifetime ~ 180 min)**
- **LER integrated current = 153 Amp-hr**
- **HER integrated current = 115 Amp-hr**
- **Peak Luminosity = 5.2×10^{32} /cm² /sec**
- **Averaged luminosity over 72 hours ~ 2×10^{32}**
- **Feedbacks are all working!**
(Transverse, Longitudinal, RF, Woofer)
- **One LER Arc recovered nicely from a bad vacuum leak (0.1 Torr of tunnel air)**
- **Injection is often 100% efficient at over 2 mA per second at 10Hz**

PEP-II Bunch Injection HER

Print Exit

Bunch Currents

Current Transformer

Raw-Ped

DCCT-Ped **724.581790 mA**

equiv mA

DI/DT **-74.986 uA/sec**

Filled Buckets **1059**

Linear **160.58 min**

Fit Lifetimes based on

10 Seconds

Exponential **160.65 min**

BIC STATE: **Quiescent**

STOP

INJECT

Calib Status

All old

Goal Status


Okay

MPG Status


MPG on/BIC off

Injection Stopping

DCCT Current; 5 second bins; 20 minute full scale




Electron Lifetime (min)




Electron Current (mA)

Positron Lifetime (min)




Positron Current (A)

LER Integrated Current vs Time



MIN: 20 100
MAX: 153:26
MAX-MIN: 133:16
22-FEB-99 08:24:48

LER Straight Vacuum Pressures vs Current





I⁺ (A)


24-FEB-99 07:46:53

LER Straight Vacuum


et
Lifetime




Pump
Pressure



LER Vacuum Pumps: Arc




LER Arc Pressure vs Current



22-FEB-99 08:51:51 I⁺ (A)

dP / dI vs I



$P = 1.8 \times 10^{-8} \text{ T}$

No Beam


$I^+ = 0$

SEM Adjs.
Volts 820
Gain 1000
OP Prot. Y

BAR MODE PLOT

N Subtraction (Switches) DataLog N

1.00e-07 Torr



Begin Mass = 1

Dwell = 16

100 = End Mass

BAR MODE PLOT


N Subtraction (Switches) DataLog N

1.00e-07 Torr

$P = 4.4 \times 10^{-8} \text{ Torr}$

Beam = 340 nA

$I^+ = 340 \text{ mA}$





SEM Adjs.
 Volts 820
 Gain 1000
 OP Prot. Y

Begin Mass = 1 Dwell = 16 100 = End Mass

PEP-II B-Factory


Longitudinal Feedback Kicker






Low Energy Ring Longitudinal Kicker


a) Osc. Envelopes in Time Domain




b) Evolution of Modes




c) Exp. Fit to Modes (pre-brkpt)




d) Growth Rates (pre-brkpt)




e) Exp. Fit to Modes (post-brkpt)



f) Growth Rates (post-brkpt)




LER, modes 780-800, growth rate vs. current, 1999-02-12





LER Bellows Temperature


$I^+ = 650 \text{ mA}$




Bellows Temperature and Current vs Time



PEP-II Interaction Region



ALBERT
E. B. B. B.
Dec. 14, 1994



Cooled S.R. Dump

γ Flux


Lead Converter


Fused Silica

P.M.T.


— Radiation Shielding Not Shown —

Luminosity Monitor and Chamber








HER Downstream IR-2 Transition Q5 to "Fant" Chambers




First Measured Luminosity 10 Nov 98

- ☛ 0.6 mA in single HER bucket
- ☛ 1.3 mA in single LER Bucket
- ☛ Stays stored even when not centered
- ☛ \mathcal{L} from deflection beam sizes and currents $\sim 2 \times 10^{29}$
- ☛ \mathcal{L} from radiative Bhabha rate $\sim 2.7 \times 10^{29}$
- ☛ 11 Bunches gave ~ 11 times luminosity




PEP-II Luminosity Record - Dec. 10, 1998



$\mathcal{L}_{\text{measured}} = 8.0 \times 10^{31} \text{ cm}^{-2} \text{ sec}^{-1}$ $I^+ = 260 \text{ mA}$ $\Sigma \Delta_y = 14 \text{ } \mu\text{m}$ $\tau_+ = 24 \text{ min}$
 $I^- = 84 \text{ mA}$ $\Sigma \Delta_x = 320 \text{ } \mu\text{m}$ $\tau_- = 470 \text{ min}$



Vertical Beam-Beam Scan



Y Position (μm)


21-FEB-99 05:02:25

PEP-II Horizontal and Vertical Beam-Beam Scans




PEP-II Horizontal Beam-Beam Scan at High Current

Note the distorted scan due to beam enlargement when the two beams are separated by about one sigma.



PEP II FRACTIONAL TUNE DIAGRAM / MP

Y tune



26
23
22
21

$\gamma_x = 38$
$\gamma_x = 24$

(-77697 / -87512)
(84241 / 86967)

DESIGN
 LER (.570 / .642)
 HER (.612 / .633)

as per M. Donald / 11.03


MEASUREMENT PAUSED

RMS:10

TRACE A: X Spectrum
A Marker

85 900.00 Hz

LER
-119.864 dBm




Center: 83 kHz

Span: 20 kHz

TRACE B: Y (Sum) Spectrum
B Marker

78 725.00 Hz

Y (Sum) Spectrum
-117.554 dBm



Center: 83 kHz

Span: 20 kHz

* pilot bunch
fine measurement

first pilot
measurement

0.6302 } e⁺
0.5775 }

Single bunch
tunes


MEASUREMENT PAUSED

RMS:10

TRACE A: X Spectrum
A Marker

77 731.250 0 Hz

HER
-135.104 dBm




Center: 78.5 kHz

Span: 5 kHz

TRACE B: Y (Sum) Spectrum
B Marker

78 720.312 5 Hz

HER
-113.843 dBm





Center: 78.5 kHz

Span: 5 kHz

0.5702 } e⁻
0.5775 }

MEASUREMENT PAUSED

RMS:10



*tune monitor
during collision*



$I^+ = 613 \mu A$

$I^- = 278 \mu A$

*first rat
measurement*

MEASUREMENT PAUSED

RMS:10




Beam-Beam

Tune Spectra


A_x (dB)
 A_y (dB)

amplitude [dB]



$N_B^{e^-} = 786$
 $N_B^{e^+} = 786$

$L [10^{30} \text{ cm}^{-2} \text{ s}^{-1}]$





vertical beam separation [μm] $\xrightarrow{\Delta y (\mu\text{m})}$

$I_{e^+} = 450 \text{ mA}$

$I_{e^-} = 315 \text{ mA}$

$(\Sigma y = 11 \mu\text{m})$





e^+ current \times e^- current / Nbunch

March 1, 1999

Maximum PEP-II Tune Shifts

Design tune shift = 0.03


e^+ x tune shift ~ 0.032

e^+ y tune shift ~ 0.017

e^- x tune shift ~ 0.031

e^- y tune shift ~ 0.013

PEP-II Luminosity vs Time



MIN: -033744
MAX: 504.4453
MAX-MIN: 504.4791
25-FEB-99 11:13:22

LAST DATA POINT: 10-FEB-1999 11:12:48

PEP-II Luminosity Record $5.2 \times 10^{32} / \text{Cm}^2 / \text{s}$ February 8, 1999

PEP-II Bunch Injection
Currents/Luminosity

Exit

Feb 08, 1999 13:07:07.090

HER

LER

Ring Current

353.847 ma

680.611 ma

Ring DI/DT

-16.376 ua/sec

-236.301 ua/s

Ring Lifetime

359.918 min

Single Bucket Number

20

24

Bucket Current

0.5413 ma

0.8688 ma

Bucket Lifetime

10.938 min

-0.298 min

PR02 CH130

PR02 CH131


Luminosities

1.144


522.730

Background Detectors and Groups

Detector	Purpose	Groups
X-Ray Spectrometer	SR spectrum	CSU + LBL
Silicon PIN Diodes	On beam pipe	Stanford U.
Straw Chamber	Tracking in SVT volume	Tennessee, et al.
MiniTPC	Tracking in SVT volume	Orsay, LBL, Cincinnati
Silicon Strip Detector	BaBar prototype	UCSD + BaBar SVT
Scanning Crystal Ring	MeV photons	Annecy, Saclay
miniSOB H2O Cherenkov	DIRC backgrounds	Cincinnati + LBL
RPC+Iron Stack	BaBar prototype	Wisconsin + BaBar IFR
RadFETs	Integrated dose	Brunel, Maryland
Calorimeter Crystals	Energetic photons	Brunel, SLAC



Current-dependence of LER ring-averaged pressure



HER Commissioning Results

<u>Parameter</u>	<u>Units</u>	<u>Design</u>	<u>"Best" by Feb 22, 1999</u>
Energy	GeV	9.0	9.0, ramp to 9.1 and back
Single bunch current	mA	0.6	12
Number of bunches		1658	1658
Total beam current	A	0.995	0.75
y/x coupling	%	3.0	down to 0.8
RF voltage/cavity	MV	0.70	0.79
Synchrotron tune		0.045	0.0447
Bunch separation	m	1.26	0.63<--->2200
Chromaticity		-43, -54 (natural)	-43.6, -55.4 (natural)
Beam Lifetime	hours	4	10 hrs @ 50mA 8 hrs @ 270mA 2.5 hrs @ 725mA
Maximum Injection Rate	mA/s	2.1 @ 60Hz	2.5 @ 10Hz

LER Commissioning Results

"Best by Feb 22. 1999"

<u>Parameter</u>	<u>Units</u>	<u>Design</u>	<u>"Best by Feb 22. 1999"</u>
Energy	GeV	3.1	3.1
Single bunch charge	mA	1.3	7.0
Number of bunches		1658	1658
Total charge	A	2.14	1.171
RF voltage / cavity	MV	0.85	0.80
Synchrotron freq.		0.045	0.024
Bunch separation	m	1.26	1.26 ↔ 2200
Beam Lifetime		4 hours	50 min @ 800 mA
Maximum Injection Rate	mA / sec	5.9 @ 60Hz	3.0 @ 10 Hz

What is PEP-II doing to help May running for BABAR

- **Installing 13 collimators**
- **Installing larger-bore higher-power Q2 chambers**
- **Turn on four new vacuum pumps near the detector**
- **Install forward-backward tunnel shield walls**
- **Improve Arc 3 LER vacuum pumping (?)**
- **Further bake IP vacuum chambers (HER)**
- **Find operational ways to make more luminosity with less current (ie lower backgrounds)**
 - ↪ Reduce observed IP beam sized
 - ↪ Lower (raise) beta y^*
 - ↪ Increase beta x^*
 - ↪ Reduce beam emittances
 - ↪ (not necessarily compatible with maximum luminosity)

PEP-II Turn-On Schedule

- | | |
|-----------------|--|
| April 30 | PEP-II Tunnel Locked for Personnel Protection System (PPS) Certification |
| May 6 | PPS Certification Finished |
| May 7,8 | PEP-II Power Supplies and RF on Damping Rings and e⁺ Source on |
| May 9 | Beams to PEP-II |

PEP-II Summary

In a few short commissioning periods the LER has reached 1.2 A and the HER 0.75 A.

With high currents, small IP spot sizes, and many bunches, PEP-II has a measured luminosity of over $5 \times 10^{32}/\text{cm}^2/\text{sec}$.

[There was more luminosity to be extracted but it was time to install BABAR.]

Backgrounds will be a problem but we have definite paths to reduced them.

We are very excited about the upcoming PEP-II run with BABAR.