

C-band R&D

S. Fukuda

Content

(1) Introduction

- Plan for C-band Linac for Super KEKB (General)
- Each Component

(2) Status of Developments


(3) Schedule up to the Accelerator Installation in Summer of 2003

Super KEKB Requirements to Injector

1. e^+ Beam Energy  3.5 \rightarrow 8.0 GeV

(for Charge Switch

8.0 GeV e^- /3.5 GeV e^+ \rightarrow 8.0 GeV e^+ /3.5 GeV e^-)

2. Injection Charge  1.0 \rightarrow 5.0 nC (e^-)
0.6 \rightarrow 1.2 nC (e^+)

(for Larger Stored Current


1.1A e^- /2.6 A e^+ \rightarrow 9.4 A e^- /4.1 A e^+)

3. Simultaneous Injection (both e^+/e^-)

4. Smaller e^+ emittance

Higher Acceleration Field scheme

for 8 GeV e+




Accelerator's Scheme


- Frequency is C-Band ($2856\text{MHz} \times 2 = 5712\text{MHz}$)
 - \Rightarrow Positron Energy Up to 8GeV with Using C-band RF Source, which Comprises 3 Sectors of #3、 #4、 #5.
 - C-band Accelerator Design and Parameters were follows,
 - \Rightarrow 2m-long Waveguide x 2、 42MV/m
 - Attenuation Factor 0.676, Filling Time $0.365 \mu\text{s}$
 - Usage of SLED Type Energy Doublers
 - \Rightarrow High Q SLED Cavity Using the TE038 Mode
 - \Rightarrow Pulse Width $2 \mu\text{sec}$,
Field Multiplication Factor 1.84 (at $Q=130000$)
- Then Operating Required Klystron Output Power is 40MW.

RF Block Diagram for C-band from #3 to #5 Sector

RF System Diagram C-band Plan(example)




Present Layout of Unit Sector



KEKB Review030211

Gallery Layout Plan

Proposed Layout of Band Unit Sector




Compact Modulator using
Inverter DC Power Supply
(Below)


Proposed Klystron Gallery Layout (Up)

Proposed C-band Modulator Configuration

*Present Configuration of
Modulator and Klystron*



Proposed Configuration




Items for Developments

- **RF-Source** (50MW Klystron was already developed)
 - (1) **Compact Modulator's** Development
 - (2) Driver 100kW Klystron Development
 - (3) Development for an **RF Window** Capable to feed 50MW with one window.
 - Need to Construct Resonant Ring to test.
 - (4) **Total Performance Test for 50-MW Operation**
- **Accelerator Guide**
 - (1) Design and Manufacturing the half-scale **c-band 1-m long accelerator guide**.
 - (2) Design and Manufacturing a **CERN-LIPS type SLED**.
 - (3) Development of necessary waveguide components, such as the Beathe-hole coupler, waveguide with vacuum port, 3 dB hybrid, **SiC dummy** load etc..
 - (4) **High-power test in the test bench**
 - (5) **Installation to the beam line and acceleration test**


Modulator Design

Basically the same pulse-forming circuit is applied to the new modulator.

The rectifier and charging circuits are replaced to the compact inverter dc power supply.



Circuit Diagram



Simulation of output pulse

Klystron Assembly Using Old 60-MW Klystron Tank

TENTATIVE

TOSHIBA PULSED KLYSTRON
AMPLIFIER
E3746

Toshiba E3746 is a C-band high power amplifier klystron designed for linear accelerators. The E3746 delivers 60MW peak output power in 2.5 μ pulses. Output power is extracted through two MRFIC standard waveguides in parallel. One port output is also possible with the specific power requirement. The electron beam is focused by a permanent electromagnet. The specific focusing electromagnet V7-60020 is available. A secondary diaphragm cathode is employed, ensuring high reliability and long tube life.



□□□

GENERAL CHARACTERISTICS

Electrical	H	M	W	Units
Heater Voltage	---	---	110	V
Heater Current	---	---	5.2	A
Heater Surge Current	---	---	7	A
Heater Warm-up Time	---	100	---	min
Peak Drive Voltage	---	---	370	kV
Peak Drive Current	---	---	314	A
Beam Resistance	---	1.53	---	μA/V ²
Frequency	---	5712	---	MHz
Peak Output Power	60	---	54	MW
Efficiency	40	---	---	%
Drive Power	---	---	500	W
Pulse Duration (Output)	---	---	0.2	μs
Pulse Duration (RF)	---	---	2.0	μs
Load VSWR	---	---	1.2	---
Ground	Tube	Flap	---	---
Electromagnet current	---	50	---	A dc
Electromagnet voltage	---	250	---	V dc

*The information contained herein is presented only as a guide for the application of our products. No responsibility is assumed by TOSHIBA for any infringement of patents or other rights of the third parties which may result from its use. No license is granted by implication or otherwise under any patent or other rights of TOSHIBA or others.
 *The information contained herein may be changed without prior notice. It is therefore recommended to contact TOSHIBA before proceeding with the design of equipment incorporating this product.

- 50MW Klystron(left)
- Coil OD 600 φ
- Core Window Size for 330kV
- We have an experience, but reliable? **Maybe OK**
- For test in this year, old 60MW klystron tank is usable at first.
 - Tank OD 700 φ
 - Flange OD 850 φ
 - (Example⇒center drawing)
- Existing Tank OD 600 φ
 - Flange of tank OD 750 φ
 - ⇒**Redesign of tank or try to fit the coil to old tank**

SB Klystron

Existing C-band 200kW klystron for weather observation station (MELCO) :5.3GHz

⇒Retune to **5.712GHz**

Similar operating scheme performed by the present sub-booster (100kW at the 30kV) is expected.

It is possible to feed C-band klystrons if the rectangular waveguide (WRJ-5) is used.

⇒Good cost performance

Constant-temperature water is necessary to keep the drive line constant.

(±0.1 degree fine controlled water)

Phase stability, Minimum phase jitter is required for the C-band case.

⇒It is necessary to study the phase stability intensively.



Design Guide of C-band Accelerator

Basic Design of C-band Unit

Output Power from C-band Kly. 40 MW
 Loss in the Waveguide 4% *
 Multiplication Factor of SLED 0.41 *
 Divide the power to two Acc. 1/2 =
 Required Power in for an Acc. Guide 58.8 MW

For Beam Study in Summer of

Output Power from C-band Kly 40 MW*
 Loss in the Waveguide 4% *
 No SLED in Summer 1.00 *
 Use only one 1m ACC. 1/1 =
 Input Power for one ACC. Guide 14.4 MW

Tentative C-band 2m Acc. Guide Design

	2a	v _g /c	r ₀	Power
Top	14.00	2.8%	67.5	58.8
Middle	12.27	1.8%	75.6	34.8
End	10.51	1.0%	84.8	14.4

Accl Field = 42.6 ~ 38.1 MV/m
 Filling Time τ_f = 380 nsec
 Attn Constant = 0.703

A-type 1/2 scale Design

	2a	v _g /c	r ₀	Power
Top	12.44	1.9%	74.8	34.4
End	10.41	1.0%	85.3	14.5

Accl Field = 41.2 ~ 39.0 MV/m
 Filling Time τ_f = 234 nsec
 Attn Constant = 0.434

Manufacturing Principle for a C-band No.1 Accelerator Guide

- Scaling down of Existing S-band Acc. Guide (Disk-Loaded Structure) to half size

Utilizing the technology accumulated in the S-band project effectively. If Scaling down is not enough, additional modification is carefully introduced.

- Manufacture a C-band 1 m long Acc. Guide, based on a KEK S-band A type 2 m long Acc.

2 m long Acc. Guide is desired in future, but at first 1 m long Acc. Guide will be manufactured considering the manufacturing process. There is a possibility that 2 m Acc. Guide = 1 m + 1 m.

We have a rich manufacturing Documents on S-band 2 m long Acc. Guide.

RF Pulse Compressor

- Parameter Comparison between KEKB-SLED and Proposed LIPS-type SLED

	KEKB-SLED	LIPS-type
Resonant Mode	TE015	TE038
Diameter	20.51cm	22.17cm(Scaled)
Length	33.59cm	29.8cm(scaled)
Frequency	2856.00 MHz	5712MHz
Cavity Q(theory)	107000	146970(Expected)
Cavity Q(Mes)	97000	127800(Expected)
Coupling β	6.4	9~11

Both sizes are almost the same and previous experiences are utilized to this new compressor. Install to Gallery is easy.

C-band components R&D status

• **Toward 2003 Summer Beam test at KEKB Linac**

(1 Pulse Modulator + 1 Klystron + 1 Accl. structure 1m-long)

- **Klystron (Toshiba 50 MW C-band Klystron)**
- **Pulse Modulator (Compact type)**
- **Sub-booster klystron (weather observation 200 kW Klystron is modified to 5712 MHz)**



Already Fabricated

- **Accelerating structure #1 (2pi/3-mode, scaled down from S-band)**
Under Engineering design (parameter tuning)
- **Wave guides, RF Window, Flange**
Under fabrication, partly finished
- **3-dB Hybrid, Dummy load**
Under Engineering design (parameter tuning)

Current Status (1) (at Feb. 5,


2005)

- **Compact Modulator with an inverter DC power supply was installed and the test was started from Feb. 3, 2003.** (right top photo) 。 Resistive load test first and then klystron load test. Running and Durations for noise will be evaluated.
- **100kW SB-Klystron for C-band was tested at beam voltage of 28.5 k V.** (right bottom photo) . Output power of 1.5kW (factory data was 4kW) was obtained and it is enough at the first test. Transistor 8W amplifier of NEC was also tested in this operation.



Current Status(2) (at Feb.5, 2003)

- **Heater test** and **low voltage emission test** of the **50MW C-band klystron** (Top of right photo) , and **magnetic field measurement of focusing coil** of the klystron (Bottom of right photo) were finished.
- From Feb. 10, 2003, **assembling the klystron on the pulse transformer tank** and **beam test** will be started. Then reassembling and rf-test will be scheduled from Feb. 17, 2003.



Mix-Mode RF Window (By Kazakov)





Figure 5.15: High power model of 53mm mixed-mode window.

- Reduced Electric-field at the edge combining a TE₁₁-mode and a TM₁₁ mode.
- Possible to use the large diameter ceramic, though structure is more complicated. (Diameter of 53mm for X-band).
- One window configuration for 50 MW output power.



Calculation and Measured Results

UG407/U (FUAR48) 4-0.8キリ4-0.3キリ4-0.3キリ4-0.8キリ交換可能ディスクWRL-48 (WRJ-5)






Designed Window and Cold Measurement (Left top and bottom)

Analysis of Ghost Mode in Window (Below)



KEKB Review030211


Test Layout of C-band Accelerator Processing in Accelerator Construction Hall



RF Measurement of Standard Cavity for the Acc. Guide in KEK



Left photo shows the standard cavity to give the standard frequency for other manufactured Cavity.




Accelerator Manufacturing Status in MHI and KEK



Due to the super-fine lathe trouble of MHI, final machining of the disks will be finished in KEK.

Left: first machined disks in MHI
Below: Coupler and measuring jig



Schedule up to Summer

We have a schedule to install an 1m-long accelerator guide in the beam line of S-band KEBB linac making use of the **summer** shut-down (**only a chance** to install it in this year). Necessary tests are planned with this schedule.

50-MW Klystron test will be started from February 17, 2003 for 2 weeks.

Evaluate the modulator performance, check the tank assembly and waveguide components. Evaluate the driving system from the master oscillator to SB klystron.

Resonant Ring Test will be started from end of the March for about a month.

Evaluate the capability of a Kazakov window with 50-MW power.

High-power test of 1m-long accelerator guide up to 40MV/m will be started from the beginning of July for 1 month.

SiC-dummy load and hybrid are also planned at the same time.

Then 1m-long accelerator guide is installed in the #4-4 unit of the KEBB linac.

All test stand components are moved to #4-4 in the Klystron gallery.

Beam acceleration test will be proceeded in this fall.

Toward 2004 Spring Beam test at KEKB Linac

(1 Pulse Modulator + 1 Klystron + 1 RF compressor + 2 Accl. structures 1m-long)

and new RF test stand

- **Accelerating structure #2 (New power coupler design)**
Under basic design
- **RF pulse compressor (LIPS-type TE038-mode)**
Under basic design
- **New RF test stand construction**
(Because all components of the test stand are moved to #4-4 in Klystron Gallery)
Demanding the budget for new bench
- **High Power test of accelerator structure #2 in the new RF test stand**
- **High power test of pulse compressor in the new test bench?**
Or directly install in the klystron gallery?
- **Beam test using the pulse compressor in 2004 spring.**