

# IR Vacuum Chamber Basic design consideration for SuperKEKB

22 Feb. 2005 KEKB Vacuum Group Ken-ichi Kanazawa

# Contents

- From KEKB to SuperKEKB
  - Experience in KEKB and Design Principle for SuperKEKB
- Preliminary Design Layout of IR Vacuum Chambers
- Summary and Next Step

From KEKB to SuperKEKB Synchrotron Radiation (SR) (1)

#### KEKB

- On the whole, COOLING IS NOT SUFFICIENT.
- For the incoming beam line, SR from far magnets was not considered seriously.

### SuperKEKB

• Provide cooling every possible SR irradiation.

# From KEKB to SuperKEKB Synchrotron Radiation (SR) (2)

### KEKB

- The exact path of the SR from QCS and its spread were not strictly taken into account in the first design.
- This caused a high temperature at unexpected portions of a vacuum chamber.
  - Deformation of vacuum chamber
  - Motion of magnets.

- The design of QC magnets in the LoI looks trying to give a sufficient clearance for the SR down to QC2.
- The design of the beam duct layout also tried to avoid the SR.
- However, the design should be checked against the fact that the two beams and the SR don' t lie in the same plane.

### From KEKB to SuperKEKB Detector Background

#### KEKB

- Back scattering of the SR from QCS by a HER Al beam duct became a noise source. (Cu has a smaller cross section of the back scattering than that of Al.)
- Shields against the detector background should have been incorporated from the first design.

- Chamber material: Cu (cooling, shielding, small back scatter of SR)
- Beam ducts avoid the SR down to 8m (HER downstream) and 5m (LER downstream) from IP.
- Shield should be taken into consideration from the first design.

## From KEKB to SuperKEKB Higher Order Mode (HOM) (1)

#### KEKB

- The HOM power turned into heat in IR is, in the unit of the loss factor, around 474 V/nC.
   (Estimated from the temperature rise of cooling water)
- Heat up of the bellows will be unacceptable level in Super KEKB

- Extrapolation from KEKB gives as a heat by HOM about 100kW ×(bunch length factor).
- Is the compact HOM absorber possible?
- The cooling for HOM will be a big problem.
- The comb type bellows is expected to be durable.

## From KEKB to SuperKEKB Higher Order Mode (HOM) (2)

#### KEKB

- Avoid a local cavity structure as possible as one can.
- Flange gap is filled with Helicoflex



- Design principle of the inner shape of chambers is same as KEKB.
- The pump slot must be designed carefully not to cause the heat up of NEG.
- Flange gap will be filled MO type gasket.
  - The design of the branching part is simmiler to KEKB.

## From KEKB to SuperKEKB Electron Cloud

#### **KEKB**

• No measures



### SuperKEKB

- TiN coating for the positron beam duct to reduce multipactoring.
- Solenoid is also necessary to confine photoelectrons.

The reduction of both photoelectron yield and secondary electron yield by a TiN coated chamber.

### From KEKB to SuperKEKB Others

#### KEKB

- NEG (Non Evaporable Getter)+Sputter Ion Pump scheme.
- Bellows is welded to a vacuum chamber.
- The pressure of the positron (LER) incoming line (within 10m from IP) is higher than expected.

- The same scheme with exchangeable NEG. ( as possible as one can)
- Easily repairable design (mechanically detachable bellows etc).
- Denser distribution of pumps.

### Beam duct layout Right hand side (1)

In HER , all ducts are expected to avoid SR.
The BPM at the end of the QCS chamber is possible only if the electrodes clear the inner bore of QCSR.



### Beam duct layout Right hand side (2)

•The space for the pump must be reserved in the magnet.



### Beam duct layout Left hand side (1)

Flange connection in the bore of QCS-L (magic flange).The ducts of LER from QCSL to QC2LP escape SR



## Beam duct layout Left hand side (2)

•The space for the pump must be reserved in the magnet.



## Summary and Next Step (1)

### Summary

- Based on the experience in the KEKB IR vacuum system, the new beam duct layout is shown.
  - Two rings separate at about 1.5m from IP.
  - HER downstream ducts avoid SR down to 8m from IP.
  - LER downstream ducts avoid SR down to 5m from IP.
  - The comb type bellows will be used and the flange gap will be filled with MO type gasket.
  - Seeking easy repair

Summary and Next Step (2)

Next Step

- To make the design more concrete:
  - Cooling structures and pumps should be added in the design.
  - The interference with magnets must be checked and be negotiated.
  - Manageability of flange connection should be checked.
  - How to fix a beam duct should be designed.
  - HOM absorber near the branching part should be studied.