

Status of the SuperKEKB Accelerator Control System

M. Iwasaki (KEK)


for the SuperKEKB accelerator control group



Introduction

The **KEKB** accelerator is upgraded to **SuperKEKB**
x40 higher luminosity

- More precise, reliable, and robust accelerator control system is required.
- Many accelerator components are upgraded.



Reliable and robust network system is required.

Device controllers (software/hardware) for the
accelerator components should be upgraded.

What we did in JFY2013

1. New network system construction

Wider band-width (100MbE → 10GbE),
Redundant system, New network configurations,
Wireless LAN system installations, ...

2. Device controller upgrade & implementation

Vacuum system, LLRF, Magnet power supply,
Safety system, QCS cryogenic monitoring system, ...

3. Additional new data archiving system

4. Beam abort system R&D

5. Timing system R&D

6. Renovation of the computing room


SuperKEKB Control System

- **EPICS is used as the main software to control the accelerator**


2 layer model

- **OPI (Operation Interface)** --- operation programs on central servers
- **IOC (I/O Controller)** --- equipment controls on frontend computers
- **Scripting Languages are used for the operation programs**

SAD Script/Tk Python/Tk Tcl/Tk




SuperKEKB Control Network System



Star network topology

- Main network switch (core switch) is located at the SuperKEKB CTL room.
- All network switches (edge switches) in the 26 sub CTL rooms connect to the main network switch.



Upgrade of the network system

In JFY2013, the control network system is upgraded.

1. Wider band-width data transfer (100MbE → 10GbE)

Replace 100MbE switches to 10GbE ones.

2. Redundant system

- Install additional optical cables.
- All edge switches are connected to the core switch via both 10GbE and 1GbE lines, and form the active/standby configuration.

3. Direct connection btw SuperKEKB and BelleII

- Install optical cables to make direct connections.
- Install 10GbE switches for higher speed data transfer.


4. New network configuration

- Apply VLAN segmentation into the SuperKEKB control network.
- Change Network connections btw SuperKEKB control network and KEK laboratory network to enhance network security.

5. Wireless LAN system installation


SuperKEKB tunnel, AR, sub-control rooms, power equip. buildings

10GbE Network Switch Installation




We install ~30 10GbE switches in Feb. 2014,
and change the network configurations.
(Redundant connections, VLAN segmentations)


KEKB-Belle Network Connection



SuperKEKB-BelleII Network Connection



SuperKEKB-BelleII Network Connection



- SuperKEKB & BelleII are directly connected
- Wider bandwidth data transfer (10MbE → 10GbE)

Optical cables are installed in Dec. 2013

Network switches are installed in Feb. 2014

VLAN segmentation for SuperKEKB

- We use EPICS to control the accelerator.
- EPICS uses UDP broadcasts to communicate btw IOC & OPI.
Many UDP broadcast packets in the control network.
(~90% of the total network traffic)
- More UDP broadcasts in the SuperKEKB network.
Accelerator components with Ethernet interface also receive the UDP broadcasts, and cannot work properly.


**We apply VLAN segmentation
to protect the accelerator components**

SuperKEKB control network consists of

1. EPICS network (for EPICS IOC and OPI)
2. Device networks (for accelerator components)

VLAN segmentation for SuperKEKB


In Feb. 2014, we apply VLAN segmentation for the SuperKEKB control network.



We have tested the new VLAN segmentation


→ IOCs in the EPICS network can control the devices in the device network.

Network reconfiguration to connect with the KEK network



We changed the network configuration in Aug. 2013.
→ **Enhance the security**

KEKB
Many computers connect to both KEK and KEKB control networks



SuperKEKB
Computers in acc. control network don't directly connect to the KEK network

Wireless LAN system installation


In JFY2012 – 2013, we installed wireless LAN into

- Whole SuperKEKB tunnel
- AR tunnel
- Power equip. buildings

for construction and maintenance of the accelerator.

All access points (~70) as well as Linac's
are controlled by 1 controller.



Wireless LAN system into the whole 3km tunnel area



We install

- **LCX (Leaky CoaXial cable) antennas for arc**
125m x 4 LCX antennas / one arc section
- **Collinear antennas for straight sections**
4 collinear antennas / one straight section

LCX and Collinear antennas in the SuperKEKB tunnel



- Select LCX and Collinear antennas with radiation hardness $>1\text{MGy}$.
- APs and PoEs in the tunnel are installed within lead boxes.
- Connector connections are wrapped with lead sheets and fixed with polyetheretherketone (PEEK) cable ties.

Device Controller for SuperKEKB

In KEKB, we mainly used **VME/VxWorks IOC** (I/O Controller)

In SuperKEKB, we use

1) VME/VxWorks IOC

CPU is upgraded

2) PLC/Linux IOC

- Yokogawa FAM3 series
- Linux running on the CPU module(F3RP61)

Apply for Vacuum system,
Beam collimators, LLRF,
Safety system, Magnet PS,
...

3) PC/Linux IOC



J. Odagiri

CPU Module
F3RP61

I/O Modules

Status of IOC Upgrade & Implementation

- **Full Replacement in progress**
 - Vacuum Control VME IOC + CAMAC → PLC IOC
 - LLRF Control VME IOC + CAMAC → μ TCA IOC + PLC IOC
 - Interface to PPS VME IOC → PLC IOC
- **CPU Upgrade of VME IOC**
 - Magnet PS in progress
 - BPM start soon
 - BT planning
- **VME IOC implementation**
 - Beam Abort System in progress
- **PLC IOC development & implementation**
 - Next page

Status of F3RP61 (PLC CPU module) Implementation

J. Odagiri


FY2013

- Interface to the Personnel Protection System
- LLRF (used with μ TCA system)
- Vacuum system
- Current stability controller for the high current Magnet PS

Things to do in FY2014

- Interlock system for the Magnet PS system
- Tilting Support (SX Magnet) Control
- BT
- Dumping Ring

ARCNET and Magnet Power Supply



Version up of the PSICM

(Power Supply Interface Controller Module)

- Interface/Controller card plugged in power supply
 - Microprocessor is embedded
 - ARCNET controller and driver
 - Timing signal input to start synchronous ramping
- New version of PSICM
 - Support high speed communication (10/5/2.5Mbps)
 - Support high resolution Power Supply (24/20/18/16bits DAC)
 - Fully compatible to the current version for the Magnet PS
 - Redundant timing signals
 - More reliable connectors

Old Version



New Version
(Prototype)



Magnet PS Control System

- FY2013 Status

- New PSICM

- Development of the prototype ver.2 → done
 - Final tuning of the firmware → in progress
 - First mass production (1000 pcs.) → in progress

- FY2014 Plan

- New PSICM


- Second mass production (2000 pcs.)
→ depends on budget
 - Installation

- IOC/OPI Software development

- modification from KEKB version

Data Archiving System

- **KEKBlog** as a primary data archiving system (file based logging system)
- **CSS(Control System Studio)-based Archiver + PostgreSQL**
as the 2nd option data archiving system



Data Archiving System




From October 2013, we monitor the QCS cryogenic system with the new archiving system (CSS + PostgreSQL).

→ Store ~300 points data every 5 seconds.

Beam Abort System

T. Naito, A. Akiyama, S. Sasaki


We have developed the faster response Beam Abort System for SuperKEKB
E/O conversion, optical cable to transfer the signal, remove low-pass filters
→ Response time improved from 100 μ s to 20 μ s



Beam Abort System

T. Naito, A. Akiyama, S. Sasaki

- JFY2013 System check using the prototype system.



- JFY2014 Installation of the new beam abort system.


Timing System for positron injection

H. Kaji, K.Furukawa (Details in the Kaji-san's talk)

In SuperKEKB, we construct the positron Damping Ring

→ Positron injection timing scheme become complicated

To account for DR, new timing system for e^+ injection is required



Wire Scanner System

Wire scanners are used as beam profile monitors at Linac and BT.

Control System is upgraded

1. CAMAC retired.


2. Event Receiver is installed.

- It enables the multi-beam operations.
 - The 1st IOC using the new version of FPGA and firmware
- ⇒ This experience is helpful for upgrade of the Main Trigger Station.

3. New functions are integrated

- Change wire speed during the scan.
 - Capability for multi-mode operation
 - Synchronization with BPM *on-going*
- ⇒ for collection of beam position and current, pulse-by-pulse.

New system (architecture)



Three systems have already installed and two of them are operated.
Installations of a few more wire scanners are planned.

Renovation of the computing room

Before the renovation




Renovation of the computing room



Last summer, we removed old server racks, old electrical panel boards, power and signal cables.


Renovation of the computing room



We removed old cables (3t in total).

Renovation of the computing room

Electrical panel boards are renewed



Renovation of the computing room

New server racks in the computing room



Summary

***Upgrade of the accelerator control system
for SuperKEKB is in progress***

In JFY2013, we did

- New network system construction
- Device controller upgrade & implementation
- Additional new data archiver construction
- Beam abort system R&D
- Timing system R&D
- Renovation of the computing room

Summary

In JFY2014, we should do

- Network system for damping ring
- New computing server system
- Device controller upgrade & implementation
- Beam abort system installation
- Timing system upgrade
- Renovation of the control room console system
- Accelerator operation equipment


New alarm system, task launcher, operation panels, ...

for the 1st SuperKEKB operation in 2015.


Backup slides

Wireless LAN in the SuperKEKB tunnel

We measured the wireless LAN network speed in the SuperKEKB tunnel.



Wireless LAN system Installation into AR



Wireless LAN system
into power equip. build.

Access Point

EPICS on PLC

- ◆ **VxWorks CPU was available on PLC (Yokogawa, Mitsubishi)**
 - ✧ Besides normal sequence / ladder CPU
- ◆ **Yokogawa starts to provide Linux (2.6) on PLC CPU (F3RP61)**
 - ❖ Brave enough to choose open source environment
 - ✧ We negotiate with Yokogawa to remove any license issues
 - ❖ Odagiri/KEK, Uchiyama/SHI-RIKEN, Yamada/KEK made much effort to realize EPICS implementation, (but no need for asynchronous records)
 - ❖ Takuya-Nakamura/MSK-KEK, et al, tailored the environment for KEKB
 - ✧ Procserv, pcmon, NFS, ...
- ◆ **Four F3RP61-based IOCs are used in KEKB operation**
 - ❖ Three since September 2008, and another later, four in total
 - ❖ Beam mask controllers and Pulsed-quad controllers
 - ❖ No trouble at all, they run more than 8 months
- ◆ **~20 new IOCs are also used in J-PARC operation now**

F3RP61 (e-RT3 2.0)

Linux 2.6.24

PPC 533MHz

128Mbyte RAM

100BaseTx x2

USB

IEEE1394

Serial


PCI

I/O Bus for FAM3 Module Interface

can access to mature FAM3 I/O Modules

Can be combined with conventional ladder CPU

Software development environment (ELDK)




**KEKB Beam mask
controller**






Simple Usage under EPICS


Conventional PLC usage with asynchronous access



PLC usage with F3RP61 with only synchronous access and maybe with sequencer



If necessary, we can combine



Number Of F3RP61-based IOC

Group	Expected numbers (at T = 0)
RF (including LLRF)	13 + 2
Vacuum	14
Magnet/Magnet Power Supplies	11 + 3
Personnel Protection System	8
Beam Monitor	1 + (?)
BT	2 + (?)
Dumping Ring	?
Helium Refrigerator	1
Total	> 39 + (?)