

The background of the slide features a dynamic, abstract pattern of glowing blue and purple lines that curve and flow across the frame, resembling particle trajectories or light trails. This pattern is set against a dark, solid background on the right side of the slide.


Status of beam transport lines

SuperKEKB review

2019.7.9

T. Mori, BT group

Contents



- Modification for Phase-3
 - Septum leakage field suppression
 - Wire scanner (WS) update
 - Fiber loss monitor (LM) installation
- Issues found in Phase-3
 - DR extraction septum PS trouble
 - BPM
 - Rejection of Linac 1-pulse modulation
 - Emittance increase
- Future plan
 - Modification of radiation safety system for getting more Linac&BT study time
 - Construction of beam diagnostics line

Modification for Phase-3


- Leakage field suppression for MR injection septum
- Wire scanner update
- Fiber loss monitor installation

Effect of septum leakage field


- It was found that septum leakage field from fringes might not be negligible for MR

LER (sler_1689.sad), 1000 positrons, 50 Hz injection, RFSW, RAD, FLUC, NOINTRA

Y. Ohnishi







Without leakage field from septum





With leakage field from septum

- Assumption for leakage: $BL \sim 1.0 \times 10^{-4}$ [Tm], $B'L \sim 0.014$ [T]

Septum leakage field measurement





Septum leakage field measurement




- $BL_{\max} \sim 2.8 \times 10^{-4}$ [Tm/fringe], $B'L_{\max} \sim 0.018$ [T/fringe]
- Both of LER/HER MR-ducts on septa was replaced with new ducts made of carbon steel overall

Vacuum group

Leakage field on new beam duct



- $BL_{\max} \sim 1.35 \times 10^{-5}$ [Tm/fringe], $B'L_{\max} \sim 0.0006$ [T/fringe]
 - 20 times smaller than that of previous measurement
 - If it not enough, there is the way that the beam duct wrapped by magnetic shield



Fiber installation


- Fibers for WS and LM
- LM: both sides connected to OE module
- WS: single side connected to OE module, opposite side is blank

Wire scanner update




Wiring jig

- Wire diameter: 200 → 60 μm
 - Wire tension: 200 gf
 - PMT → fiber loss monitor as detector
 - DAQ system
 - VME event receiver, ADC, scaler
 - Pulsed motor controllers (LAN based connection)
 - Software updated



Wire scanner is tilted by 45 degrees from a horizontal plane



All the wires of 11 WSS
were replaced



Beam loss measurement with fiber loss monitor

- Beam status
 - Electron: 1bunch 12.5Hz 0.7nC
 - Positron: 1bunch 12.5Hz 0.6nC
5.85e-5 C/hour in total
 - N: 0.02 μ Sv/h, γ : BG @ BT escape door
 - N: 0.016 - 0.02 μ Sv/h, γ : BG @ ARS cable introducing port
- Currently 5.76E-4 C/hour is allowed by radiation safety; about 10 times larger
- 2-bunch, 25Hz, 2nC/bunch injection → 12 times larger if linearly scaled
- Loss rate should be kept less than threshold value

Fiber loss monitor



T. Mimashi




- Beam loss could be successfully reduced by BT orbit tuning
- Ready for 2-bunch, 25Hz, 2nC/bunch injection

Issues found in Phase-3

- DR extraction septum PS trouble
- BPM
- Rejection of Linac 1-pulse modulation
- Emittance increase
 - Will be reported in next presentation (N. Iida for Y. Seimiya)

DR Extraction Septum PS trouble

M. Tawada



DR extraction septum

Deflection angle (mrad)	103
Max. current (kA)	12.5
Max. voltage (kV)	2.0
Voltage stability (%)	< ± 0.01
Current waveform	full sine wave
Max. Repetition (Hz)	50
Full sin wave width(usec)	250
Magnet inductance (μ H)	5.9

2019.07.09


SuperKEKB Review




13

DR Extraction septum PS trouble

M. Tawada




Septum magnet



- DR extraction septum PS had been in trouble.
- The voltage of the main capacitor couldn't be controlled precisely.
- This failure had been disappeared during the investigation.
- It will be checked during this summer maintenance.
- Spare circuit board will be available in Jan. next year because of the global shortage of MLCC.

Issues for BPM: BT end feedback and bpm resolution



- Radius of target circle: 0.3 mm; larger target had induced beam abort
- Full width of BPM resolution: > 0.5 mm
- Asynchronous BPM readout: feedback delayed
- Difficult to keep orbit in target range




Maybe situation is severer for tighter MR optics

Issues for BPM

- Other problem
 - Old oscilloscopes (Windows XP) are still in use
 - ~10 channel of BPM signals combined and read by a oscilloscope channel
 - Installation of cables corresponding 1 to 1 BPM channel is difficult for budgetary restriction
- Solution under consideration
 - For BT end feedback (8-BPM): Libera
 - The rest of BPMs: Tektronix 12-bit ADC osc after command 'CURVESTREAM' implemented

Rejection of Linac 1-pulse modulation



This type of beams induce MR abort


- Energy modulation ~ 50 Mev
- Impossible to reject modulated beams by collimators on BT-line
- Planning to relocation of collimators where dispersion exists
 - Middle of ECS@SY3 for positrons
 - Near vertical bend on end of slope for electrons

Future plan

- Modification of radiation safety system for getting more Linac&BT study time
- Construction of beam diagnostics line

Modification of radiation safety

- Beam operation of BT is not allowed even if there are men only at opposite side of injection point (IR, BelleII)
- Divided management allows BT-dump mode operation when Tsukuba, Nikko, Oho is 'limit' or 'free' state
- Linac&BT need more study time
- Also important to reduce injection BG
- Task force organized, decided to do, detail specification development on going
- Fastest implementation: 2020 fall
- Safety is most important; we should be patient



Construction of beam diagnostics line

- Importance of keeping stable injection increases day by day
- Some people consider diagnostics system separately
- Task force will be organized

Summary

- Modification for Phase-3: successfully
 - Septum leakage field suppression
 - Overall carbon steel ducts were installed for LER/HER
 - Wire scanner
 - Fiber loss monitor installed
- Issues found in Phase-3: need breakthrough
 - Power supply trouble on DR extraction septum
 - Under investigation
 - BPM
 - Resolution and synchronization
 - Solution under consideration; Libera for BT-end feedback BPMs, 12-bit ADC osc for others
 - Rejection of Linac 1-pulse modulation
 - Collimator will be relocated to reject modulated beams
- Future plan
 - Modification of radiation safety system
 - Specific development on going
 - Construction of beam diagnostics line
 - Task force will be organized




Thank you

Backup slides


LER1 Septum Leakage Field

T. Mori
2017.11.06


測定方法



z軸方向に測定




$x = 0.0$ [mm]



$x = 15.0$ [mm]

x軸方向に測定

Fitted magnetic flux density at $V = 1375.0$ [V], $f = 2.0$ [Hz], $z = 110.0$ [mm], $I = 0.00655679396226$ [kA]



最大で20Gauss程度


$$BL = 0.5 \times 0.28 \times 20 \times 10^{-4} = 2.8 \times 10^{-4} [\text{Tm}]$$

磁気遮蔽

- SUS430 filmを用意した
 - 2種類: 2 μm , 5 μm
- 5 μm はうまく巻けなかった
- 2 μm を巻いて、アルミテープで留めた
 - 本当は6 μm 程度ほしいところ
 - 3枚くらい重ねて巻けばよかったかも？


SUS430-film あり/なし

Magnetic flux density distribution at $V = 1375.0$ [V], $f = 2.0$ [Hz], $z = 105.0$ [mm]



SUS430-film あり/なし

Magnetic flux density distribution at $V = 1375.0$ [V], $f = 2.0$ [Hz], $x = 0.0$ [mm]




MR duct reproduction

- 作り直すとして、どのくらい磁性体部を延長するか
- D8側のMR ductも作り直すか
 - HER2部分
 - 磁性体にできるならしたほうが安心
 - 末次氏によると可能とのこと
 - 上流側短管
 - ここは磁性体のカバーを取り付けねばよい
 - 作り直して入れる場合、上流側セプタムをどける必要がある


漏れ磁場：磁性体ダクト効果

小玉さんのスライドより

- 磁性体ダクトなし
- 磁性体ダクトをセプタム銅板端から25 mm突き出し
- 磁性体ダクトをセプタム銅板端から100 mm突き出し
(上流側の磁性体ダクト突き出し量)




もれ磁場が最大の場所で測定
(コア端から90 mm, セプタム板端から20 mm)




漏れ磁場は磁性体ダクトによって十分に小さい信号値まで減少.

*菊池さんの計算によると1 Gauss程度の磁場では周回ビームへの影響はない

ダクト突き出し量と漏れ磁場




- プローブの位置まで磁性体ダクトが来ていると半分程度に落ちる





MRダクト磁性体部をセパタム導体板の端から150mm程度延ばす セパタム導体板の端

Design of reproduced beam duct (LER)



R10.2: Cross-calibrate the field measurements of magnets between LTR, RTL, DR, and Linac.



IRトンネル入域中の BT dump mode化

2019.3.29

SuperKEKB Commissioning打ち合わせ

N. Iida

これは、MRの富士周辺のみをキープアウトにすることにより、筑波地区などリングの他の場所での作業中でも、BTラインでのビーム調整、ビームスタディを可能にするためにシステム変更をお願いしたいという趣旨に基づくものです。

BT dump modeでの調整について

1. BT調整の必要性

- A) Emittance 増大問題
- B) 入射ビーム調整として

2. LINAC mode

- A) 電子、陽電子をPulse-to-pulseでDumpできない。
- B) Energy profileは、BTと同等。
- C) Straight dump？

3. IR作業

- 1. どれくらいあるか？

4. BT安全システム変更


- 1. 予算はどれくらい？
- 2. 作業量は？

1. BT調整の必要性

A) Emittance増大問題

Request of injection beam from SuperKEKB

	Phase 2	Phase3 Goal	
	2018	2019~202?	
		e+	e-
$\gamma\varepsilon_x$ [μm]	< 200	< 100	< 40
$\gamma\varepsilon_y$ [μm]	< 40	< 15	< 20
$\sigma\delta$ [%]	0.16	0.16	0.07
Charge [nC]	1.5	4.0	4.0





Emittance blowup in Phase 2

Final Request from MR
 Phase2 -----
 Phase3 final -----


There is no question that
 the emittance blowup
 affects the BG.

e-




Measurement
 at the upstream
 of BT

e+



DR designed value



40 -----
 15 -----

More beam studies at BT will be needed.

LINAC Beam Studies (Oct.-Dec., 2018)

- RF Gun (M. Yoshida, X. Zhou, R. Zhang)
- Thermionic Gun
 - Tuning of Buncher (T. Natsui)
 - Q-Scan, TunC (T. Natsui and Y. Seimiya)
- 24 degree Line
 - Measurement and Correction of Dispersion (Y. Seimiya)
 - Measurement of Response and Aperture (Y. Seimiya)
 - Consistency Measurement of BPM (F. Miyahara)
- Jarc
 - Measurement and Correction of Dispersion (Y. Seimiya)
 - Bunch Compress (M. Yoshida)
 - OctoPos BPM (F. Miyahara)
- Measurement of Beam Position Jitter and Fluctuation (Y. Seimiya)
 - Binarization from Pulsed Magnet (T. Natsuim Y. Enomoto, M. Satoh, I. Satake)
 - Monitors of RF Phase and RF Induced wave
- Monitors of RF Phase and RF Induced wave (T. Miura, et al.)
- Primary side power fluctuation (T. Miura, T. Natsui)
- Investigation around Dummy Target (Y. Enomoto, H. Sugimura, T. Kamitani, Y. Ohnishi, Y. Funakoshi, N. Iida)
 - Beam Based Alignment (Ballistic Orbit, QuadBPM)
- Investigation of Solenoid magnet after Positron Target (T. Kamitani, Y. Ohnishi)
- Measurement of RF Energy Gain (T. Kamitani, Y. Ohnishi, T. Natsui, Y. Seimiya, M. Satoh)
- SY2 (N. Iida, H. Koiso)
 - Measurement of Dispersion
- Sector 3-5
 - Offset Injection (Y. Seimiya, N. Iida, T. Mimashi)
 - Fudge Factor Measurement of Quad (Y. Seimiya)
 - QuadBPM (H. Sugimura), Mover Alignment (Y. E)
- Coexistence with PF and PF-AR

... Studies especially related to the BG:
Core subjects

秋、冬のLINAC Studyでは、
Beam jitter, Energy jitter, OctoPos開発等、
様々な理解を進めることができた。

しかし、BT dump modeはMRがReadyでないとできないので、
BTの調整時間を確保するには、MR運転中にもかかわらず入
射を止めなければならない。



→少しでもBT調整の時間が取れないか？

→IR作業中にBTDump modeにできないか？

1. BT調整の必要性

B) 入射ビーム調整


LINACビームの診断ラインとしてのBT



当然LINACとBTは繋がっていて、 LINAC-BT全長の約4割を占める。
BT dumpまで調整しておけば、入射までは100m以下である。
LINACの診断ラインとしても重要。

2. LINAC mode




A) 電子、陽電子をPulse-to-pulseでDumpできない。



2. LINAC mode


B) Energy profileは、BTと同等

Dump line でも、
Dispersionは十分大きい (-3m)



2. LINAC mode


C) Straight dump ?



3. IR作業

- 今後どれくらいあるか?
 - 2020年（2021年？）夏、Belle2の作業で8ヶ月トンネル入域がある。
 - 8ヶ月間の最後の何日間かは、IR以外の作業がないことも考えられる。
 - IR関係の作業は、トラブル等により日常的に1～2時間程度の作業はあり得る。（不吉なのであまり考えたくありませんが）

4. BT dump mode



5-6月運転中の筑波入域

2019.6.19

N. Iida

木曜メンテ : 5/16, 30, 6/13
メンテ日以外の筑波入域を調べた。

2019-05-07 12:06:39	筑波入域(末次) コリメータ確認	27分
2019-05-08 10:14:34	筑波入域(石橋、照井) 真空作業	112分
2019-05-08 10:31:45	筑波入域(白井) 真空作業	
2019-05-08 10:57:23	筑波入域(大山、坂木、TNS:吉原) 放射線測定	
2019-05-09 16:43:00	筑波入域(田中(秀)、Dmytro、Bjoern、Hua) PXDメンテナンス	34分
2019-05-13 15:39:44	筑波入域(ドミトリ、ジュゼッペ) KLMの点検	37分

2019-05-07 12:33:30	筑波退域(末次)
2019-05-08 11:06:35	筑波退域(大山、坂木、TNS:吉原)
2019-05-08 12:06:29	筑波退域(石橋、照井、白井)
2019-05-09 17:17:43	筑波退域(田中(秀)、Dmytro、Bjoern、Hua)
2019-05-13 16:16:41	筑波退域(ドミトリ、ジュゼッペ)

2019-06-05 10:32:58	筑波入域(田中(秀)、Levit、Mueller) PXDメンテナンス	29分
2019-06-06 08:01:50	筑波入域(飛山) ロガー交換作業	4分
2019-06-08 09:43:31	筑波入域(中村(克)、Antonio、坪山) 電源の交換	28分

2019-05-21 01:51:57	筑波入域(大木、大澤) 電磁石点検	60分
2019-05-21 01:57:35	筑波入域(中村衆) 電磁石点検	
2019-05-25 17:15:49	筑波入域(飛山氏、MSC 田中直、MSC 白石) 冷却水調整	7分
2019-05-28 09:07:48	筑波入域(大澤) 冷却水確認	20分
2019-05-28 13:47:07	筑波入域(足立、パベル) 検出器チェック	137分
2019-05-28 14:50:23	筑波入域(ドミトリ、スワガト、クリス) KLMの点検	
2019-05-28 14:52:23	筑波入域(白井、照井) 真空作業	

2019-05-21 02:51:47	筑波退域(大木、大澤、中村衆)
2019-05-25 17:28:05	筑波退域(飛山氏、MSC 田中直、MSC 白石)
2019-05-28 09:27:37	筑波退域(大澤)
2019-05-28 15:09:18	筑波退域(白井、照井)
2019-05-28 15:51:34	筑波退域(足立、パベル)
2019-05-28 16:04:09	筑波退域(ドミトリ、スワガト、クリス)

2019-06-05 11:01:04	筑波退域(田中(秀)、Levit、Mueller)
2019-06-06 08:05:00	筑波退域(飛山)
2019-06-08 10:15:18	筑波退域(中村(克)、Antonio、坪山)

5/7-6/8 :
434+61=495分

QCS Quench時

2019-06-09 23:10:00	筑波入域(末次) 真空調査	5分
2019-06-09 23:25:15	筑波入域(大内、ZONG Zhanguo) QCS確認	18分
2019-06-10 00:37:35	筑波入域(日立プラント:遠藤、日立テクノロジー:伊佐) QCSR冷凍機真空ポンプ復旧	7分
2019-06-10 02:19:30	筑波入域(日立プラント:遠藤、日立テクノロジー:伊佐) 真空ポンプ立て上げ	29分
2019-06-10 07:20:05	筑波入域(大内、日立プラント:遠藤) 真空ポンプ立て上げ	5分
2019-06-10 10:06:22	筑波入域(照井、白井、末次) 真空作業	93分
2019-06-10 11:14:03	筑波入域(ユーサ:村瀬) 真空作業	
2019-06-10 11:16:59	筑波入域(大内、日立プラント:遠藤) 真空ポンプ作業	
2019-06-10 13:30:58	筑波入域(田中(秀)、Qingyuan、Boqun) PXDメンテナンス	30分
2019-06-10 14:10:51	筑波入域(照井、白井) 真空作業	43分
2019-06-11 14:18:33	大内氏より、筑波入域の連絡あり →飯田氏へ連絡、了承	34分
2019-06-11 14:20:25	筑波入域の為、安全Magnet立ち下げ	
2019-06-11 14:39:26	筑波入域(大内、宗、日立:遠藤) QCS点検	13分
2019-06-11 15:14:57	大内氏より、筑波入域の連絡あり →飯田氏へ連絡、了承	
2019-06-11 15:30:54	筑波入域(大内) QCS点検	43分
2019-06-11 15:36:54	筑波入域(日立:遠藤) QCS点検	
2019-06-11 15:51:32	筑波入域(宗) QCS点検	

2019-06-09 23:15:06	筑波退域(末次)
2019-06-09 23:43:02	筑波退域(大内、ZONG Zhanguo)
2019-06-10 00:44:58	筑波退域(日立プラント:遠藤、日立テクノロジー:伊佐)
2019-06-10 02:48:00	筑波退域(日立プラント:遠藤、日立テクノロジー:伊佐)
2019-06-10 07:24:53	筑波退域(大内、日立プラント:遠藤)
2019-06-10 11:21:44	筑波退域(大内、日立プラント:遠藤)
2019-06-10 11:39:53	筑波退域(照井、白井、末次、ユーサ:村瀬)
2019-06-10 14:00:52	筑波退域(田中(秀)、Qingyuan、Boqun)
2019-06-10 14:53:29	筑波退域(照井、白井)
2019-06-11 14:52:20	筑波退域(大内、宗、日立:遠藤)
2019-06-11 16:13:48	筑波退域(大内、宗、日立:遠藤)

2019-06-19 09:03:20	筑波入域(田中(秀)、Qingyuan、Felix) PXDメンテナンス
2019-06-19 09:23:44	筑波入域(西田) PCの保守
2019-06-19 09:30:03	筑波入域(照井) 真空作業

2019-06-19 09:27:20	筑波退域(田中(秀)、Qingyuan、Felix)
2019-06-19 09:29:16	筑波退域(西田)
2019-06-19 09:44:02	筑波退域(照井)

5/7-6/8 :
 $434+61=495$ 分

6/9-6/19 :
 $320+44=364$ 分



5/7-6/19 :
 $495+364=859$ 分=14時間32分