



# Overview of SuperKEKB Status


Y. Suetsugu

Accelerator Laboratory, KEK



# Contents


- Brief review since the last KEKB review (2018/3/14-16)
  - Highlights in Phase-2 (2018/3/19-2018/7/17),  
and Phase-3 2019 spring run (2019/3/11-2019/7/1)
- Key challenges for higher luminosity
  - Specific luminosity
  - Background
  - QCS quench and beam aborts
- Commissioning plan
- Summary





# Highlights in Phase-2

- Phase-2 commissioning started from 19<sup>th</sup>, March, and ended 17<sup>th</sup>, July, 2018.
- Aims of Phase-2:
  - Positron injection through the damping ring (DR)
  - Collision tuning with QCS (final focusing quadrupole magnets) and Belle II detector.
  - Demonstrate “nano-beam” collision scheme.
  - Confirm that the background is tolerable level for the vertex detector (VXD) to be installed in Phase-3.







# Highlights in Phase-2

- The injector linac has been working stably.
- Simultaneous beam injection to five rings (HER, LER, Damping ring, PF, and PF-AR) was realized in Phase-2.
  - Pulsed magnet system is working well.
- Photo-cathode RF gun has been regularly used for HER injection.
- Flux concentrator has been also functioning as expected.
  - These will be reported by Satoh-san, Zhang-san, and Enomoto-san.

Layout of injector linac



Flux concentrator for e<sup>+</sup>








# Highlights in Phase-2


- Commissioning of DR was very successful.
  - It took only a few days for injection, storage, and extraction.
- DR has been working well since Phase-2.
  - Will be reported by Mori-san.
- Emittance issues in the beam transport (BT) line have been continuously investigated.
  - Will be reported by Seimiya-san.
- Damping of bunch (Phase-3): by Ikeda

While the beam at first blows up just after the injection to the ring, the longitudinal and horizontal beam sizes well damped after 20 ms by the radiation damping.

## Operation status of DR (Phase-3)



## Longitudinal beam size (vertical) and horizontal beam size (horizontal) after injection [Streak camera] (Phase-3)








# Highlights in Phase-2

- In MR, the collision tuning was proceeded squeezing  $\beta_x^*/\beta_y^*$  gradually.
- The first physics event was observed on 26<sup>th</sup>, April, 2018.

The first event on 26<sup>th</sup>, April 2018.





# Highlights in Phase-2

- Specific luminosity ( $L_{sp}$ ) increased in proportion to  $1/\beta_y^*$ .



- This demonstrated the “nano-beam scheme” collision for the first time in a practical machine.

- But, decrease in the specific luminosity with bunch current product has been observed due to beam-size blowup.

$$L_{sp} = \frac{L}{n_b I_{be} I_{bp}} \propto \frac{1}{\beta_y^*}$$

for  $\frac{\beta_y^*}{\varepsilon_y} = \text{const.}$

$$L_{sp} \propto \frac{1}{\langle \sigma_y^* \rangle} \text{ for } \sigma_z^* = \text{const.}$$








# Highlights in Phase-2

- QCS has been working stably since Phase-2.
- Lots of quenches were triggered by beams in Phase-2.
- The quenches due to injection beams were avoided by tuning beam collimators and injection parameters.
  - Narrower apertures at collimators than those in QCS.
  - Fast beam abort system using VXD diamond sensors.
- The quenches, which might be induced by beam-dust collision, occurred twice.
  - The head of a beam collimator was heavily damaged.
  - The similar event was again experienced in Phase-3.

List of quench events

Date	Time	Quenched Magnet	Beam Line	電流遮断後の ビームアポート (HER)	(LER)	← In	Corrector name	→ Out	← In	Corrector current [A]	→ Out		
2018/4/1	2055	QC1 LP	LER			a1	b1	a2	b4	-1.13	2.97	-0.11	-0.36
2018/4/2	1929	QC1 LP	LER			a1	b1	a2	b4	-1.13	2.97	-0.11	-0.36
2018/4/9	1731	QC1 LE-H	HER			b1	a1	a2	b4	-32.57	-11.19	3.98	-0.03
2018/4/9	2006	QC1 LE-H	HER			b1	a1	a2	b4	-32.57	-11.19	3.98	-0.03
2018/4/9	2053	QC1 LE-H	HER			b1	a1	a2	b4	-32.57	-11.19	3.98	-0.03
2018/4/9	2140	QC1 LE-H	HER			b1	a1	a2	b4	-32.57	-11.19	3.98	-0.03
2018/4/10	1744	QC1 LE-H	HER			b1	a1	a2	b4	-32.57	-11.19	3.98	-0.03
2018/4/10	2156	QC1 RE-H	HER			b1	a1	a2	a3	33.20	-2.22	-1.26	0.12
2018/4/11	1421	QC1 RE-H	HER			b1	a1	a2	a3	33.20	-2.22	-2.42	0.12
2018/4/11	1525	QCSL-Cam-B3	HER			b3	b4	b5	b6	-40.30	-25.60	-17.60	14.40
2018/4/11	1845	QC1 RE-H	HER			b1	a1	a2	a3	33.20	-2.22	-2.42	0.12
2018/4/11	2023	QC1 RE-H	HER			b1	a1	a2	a3	33.20	-2.22	-2.42	0.12
2018/4/11	2115	QC1 RE-H	HER			b1	a1	a2	a3	33.20	-2.22	-2.42	0.12
2018/4/20	1433	QC1 RP	LER			a1	b1	a2	b4	0.12	-13.88	-3.96	0.27
2018/4/20	1433	QC1 LP	LER	at the same instance		a1	b1	a2	b4	1.33	2.97	-1.22	-0.36
2018/4/20	1433	QC1 RP-H	LER			a1	b1	a2	b4	1.33	2.97	-1.22	-0.36
2018/4/21	02149	QC1 LP	LER	at the same instance		a1	b1	a2	b4	0.12	-13.88	-3.96	0.27
2018/4/21	02151	QC1 RP	LER			a1	b1	a2	b4	0.12	-13.88	-3.96	0.27
2018/4/21	02213	QC1 RP-H	LER			a1	b1	a2	b4	0.12	-13.88	-3.96	0.27
2018/5/6	1128	QC1 LE-H	HER	マイナス11ms	No abort	b1	a1	a2	b4	-32.57	-11.02	4.82	-0.03
2018/5/13	245	QC1 RP-H	LER			a1	b1	a2	b4	No data	No data	No data	No data
2018/5/17	208	QC1 RP-H	LER	No abort	22.35ms	a1	b1	a2	b4	0.12	-13.88	-3.96	0.27
2018/5/17	406	QC1 RP-H	LER	No abort	34.65ms	a1	b1	a2	b4	0.12	-13.88	-3.96	0.27
2018/5/24	1717	QCSL-Cam-B3	HER			b3	b4	b5	b6	-40.30	-25.60	-17.60	14.40
2018/6/25	112034	QC1 RP	LER			a1	b1	a2	b4	0.12	-13.88	-3.96	0.27
2018/6/25	112034	QC1 RP-H	LER			a1	b1	a2	b4	0.12	-13.88	-3.96	0.27
2018/6/25	112034	QC1 LP	LER			a1	b1	a2	b4	0.12	-13.88	-3.96	0.27
2018/7/3	51417	QC1 RP-H	LER	入射中	285.9 mA	a1	b1	a2	b4	0.12	-13.88	-3.96	0.27

Damage of collimator head







# Highlights in Phase-2

- Summaries of major results in Phase-2


Major results in Phase-1 and Phase-2				
Parameters	Phase-1 (3/2/2016–6/30/2016)		Phase-2 (3/19/2018–7/17/2018)	
	LER	HER	LER	HER
Max. beam current [mA]	~1010	~870	~860	~800
Beam dose [Ah]	775.0	661.5	337.5	340.2
Min. $\beta_x^*/\beta_y^*$ in physics run (non phys.) [mm/mm]	-	-	200/3 (200/2)	100/3 (100/1.5)
Min. $\varepsilon_x / \varepsilon_y$ [nm/pm]	~-/10 . (single)	~-/10 (single)	~1.7/160 (in col.)	~4.6/80 (in col.)
Max. bam beam param.			0.0244	0.0141
Max. lumi. $L$ [ $\times 10^{33}$ cm $^{-2}$ s $^{-1}$ ]			5.55 (@1/1576/3.06)	
Specific lumi. @Max. $L$ [ $\times 10^{31}$ cm $^{-2}$ s $^{-1}$ mA $^{-2}$ ]			1.43	



# Highlights in Phase-3 2019 Spring



- Phase-3 commissioning started from 11<sup>th</sup>, March, and ended 1<sup>st</sup>, July, 2019.
- Aims of Phase-3 2019 Spring run:
  - Starting full-scale physics run with complete VXD in Belle II.
  - Accelerator and collision tunings with lower  $\beta^*$  for higher luminosity.






# Highlights in Phase-3 2019 Spring

- Fire accident in the linac building on 3<sup>rd</sup>, April.
  - The fire occurred at a room separated by a wall from the injector linac used by SuperKEKB, but **lots of carbon soot** in the power pulsed-modulators should be cleaned up before restart.
- MR operation stopped for **approximately 3 weeks** during the recovery work of the linac, and the operation finally **restarted from 25<sup>th</sup> and 26<sup>th</sup>**.
- Details will be presented by Abe-san and Furukawa-san.

Soot at terminal block



Burnt pulse modulators




Injector linac



Accelerating structure assembly room

Electron RF gun









# Highlights in Phase-3 2019 Spring





- $\beta_y^*$  was gradually squeezed and the optics with  $\beta_y^* = 3$  mm was established on 1<sup>st</sup>, April.
- LER and HER continuous injection started from May.
  - Increase in int. luminosity.
    - Realized after successful background reduction by elaborate tunings of injection parameters and collimators.
- Most of physics run was operated with  $\beta_x^* = 200/100$  mm (LER/HER) and  $\beta_y^* = 3$  mm.
  - $L \sim 0.5 \times 10^{34} \text{ cm}^{-2}\text{s}^{-1}$  at ~600 mA.





# Highlights in Phase-3 2019 Spring

- $\beta_x^*/\beta_y^*$  were squeezed to 80/2 mm on 21<sup>st</sup>, June.
- After collision tuning, the max. luminosity of  $1.23 \times 10^{34} \text{ cm}^{-2} \text{ s}^{-1}$  was recorded at approximately 820/830 mA (LER/HER, 1/1576/3.06RF), although the Belle II HV was off due to high background.
- Specific luminosity increased in proportion to  $1/\beta_y^*$ .
  - Satisfied even for  $\beta_y^* = 2 \text{ mm}$ .





# Highlights in Phase-3 2019 Spring



- Summary of major results

Major results in Phase-1, Phase-2 and Phase-3 2019 Spring run

Parameters	Phase-1 (3/2/2016–6/30/2016)		Phase-2 (3/19/2018–7/17/2018)		Phase-3 2019 Spring run (3/11/2019–7/11/2019)	
	LER	HER	LER	HER	LER	HER
Max. beam current [mA]	~1010	~870	~860	~800	~830	~940
Beam dose [Ah]	775.0	661.5	337.5	340.2	500.4	539.1
Min. $\beta_x^*/\beta_y^*$ in physics run (non phys.) [mm/mm]	-	-	200/3 (200/2)	100/3 (100/1.5)	100/3 (80/2)	100/3 (80/2)
Min. $\varepsilon_x / \varepsilon_y$ [nm/pm]	~-10 . (single)	~-10 (single)	~1.7/160 (in col.)	~4.6/80 (in col.)	~2.0/88 (in col.)	~3.8/61 (in col.)
Max. beam param.			0.0244	0.0141	0.0355	0.0197
Max. lumi. $L$ [ $\times 10^{33} \text{ cm}^{-2} \text{ s}^{-1}$ ]			5.55 (@1/1576/3.06)		12.3 (@1/1576/3.06, $\beta_y^*=2\text{mm}$ )	
Specific lumi. @Max. $L$ [ $\times 10^{31} \text{ cm}^{-2} \text{ s}^{-1} \text{ mA}^{-2}$ ]			1.43		2.9	







# Key challenges for high luminosity



- Decrease in  $L_{sp}$  with bunch current product.
- Caused by the beam-size blowup due to beam-beam effect.
  - Ex. LER  $\varepsilon_y$  6.1  $\rightarrow$  88 pm, HER  $\varepsilon_y$  20  $\rightarrow$  61 pm. ( $\beta_y^* = 2$  mm,  $\sim 700$  mA)
  - Although  $L_{sp}$  has been improved by elaborate collision tunings, but the tendency does not change.
- The mechanism has not been well understood yet.
- To be reported by Ohnishi-san and Ohmi-san.





# Key challenges for high luminosity



- High background (BG)
- From LER stored beam
  - Main BG source in LER storage mode was found to be the beam-gas Coulomb scattering. This raised the base of BG, and limited the beam currents during physics run.
- Bursts from stored beam
  - Induced CDC trips and/or beam aborts. Dusts?.
- Bursts from Injection beams
  - Induced CDC trips and/or beam aborts. Changes in energy or orbit at the linac?
- Slow change in injection condition
  - BG as well as the injection efficiency degraded gradually, even in a shift (8hours), and it was difficult to keep good injection condition.
  - Temperature dependence?
- Background issues will be reported by Nakayama-san and Iida-san.



# Key challenges for high luminosity



- QCS quenches and beam aborts
- Frequency of QCS quenches in Phase-3 decreased compared to that in Phase-2.
- However, seven quenches (two types) happened.
- [Type-1]: Caused by the malfunction of QC2LE power supply.
- [Type-2]: Very fast (3~4 turns) beam loss event! Suspected to be caused by the steered or blown-up beam which lost energy by a collision with dusts (LER).
  - Stored beam was steered or blown up abruptly and damaged a vertical-type collimator head. Similar to the case in Phase-2.
  - Also gave high radiation dose to VXD.
- Quenches, beam aborts and dust events will be reported by Ohuchi-san, Ikeda-san, Nakamura-san, and Ishibashi-san






# Commissioning plan




- Summer shutdown (2019/7/1~2019/10/15)
  - Replacement of the bellows at IP
  - Replacement of QC1L BPM cables at IP
    - These works require the retraction/insertion of QCS-L.
  - Any measures against QCS quenches if available.
  - Many other works in the machine and the Belle II.
- Autumn run (2019/10/15~2019/12/12)
  - Continue the physics run and machine tunings.

FY2019 SuperKEKB Operation Plan (2019/4/18)



FY2020 SuperKEKB Operation Plan (Not fixed)






# Commissioning plan




- Winter shutdown (2019/12/12~2020/1/16(not fixed))
  - 150 kV power line work by TEPCO
    - The electric power in KEK was restricted to less than 50 MW.
    - The MR have to be stopped. Linac, DR, and BT can be operated.
  - A vertical-type collimator will be installed into LER.
- 2020 Spring run (2020/1/16~2020/6/30 (under consideration))
  - Operation in January will be for mainly BT tuning and vacuum scrubbing.
  - Continue the physics run and machine tunings.

FY2019 SuperKEKB Operation Plan (2019/4/18)



FY2020 SuperKEKB Operation Plan (Not fixed)






# Commissioning plan



- Luminosity projection
- Discussion about the strategy to increase the luminosity has just started, on the basis of the results in this run.



- We need more discussions together with Belle II group to find the best way.

- **As a case study**, here the machine study to squeeze  $\beta_y^*$  is highly prioritized.
  - $\beta_y^*$  is squeezed step by step every four weeks.
  - Two weeks for machine study and two for physics run
  - 28 weeks operation/year
  - 1576 bunches.
- Notes
  - No improvement in beam-beam parameter.
  - Keep the present  $L_{sp} \times \beta_y^*$  dependence on  $I_b^2$ .
  - No improvement in BG situation, i.e.,  $I_{max}$  was limited by the present pressure (scrubbing effect is included).





# Summary-1



- Phase-3 has just finished.
  - Full-scale physics run has finally started.
  - The “nano-beam scheme” collision was demonstrated up to  $\beta_y^* = 2$  mm.
  - Continuous injections for both rings are available in regular operation.
  - The max. luminosity of  $1.23 \times 10^{34} \text{ cm}^{-2}\text{s}^{-1}$  was recorded at  $\beta_y^* = 2$  mm (LER 820 mA, HER 830 mA, 1576 bunches).
  - The injector linac and DR have been working well.
- Key challenges to increase luminosity
  - Low specific luminosity at high bunch current product
    - Essential issue to realize high luminosity.
  - High background
    - Limit beam currents.
  - QCS quenches and beam aborts
    - Fast abort system is indispensable for stable high-current operation.



# Summary-2



- Commissioning plan

- Plan in FY2019 is almost fixed, and we will expect ~ 7 months' operation.
  - 2019 Summer shutdown: 7/1 ~ 10/14
    - Replacement of bellows at IP, repair of QCS BPM.
  - 2019 Autumn run: 10/15 ~ 12/12
  - 2019 Winter shutdown: 12/12 ~ 2020/1/16
    - Power line work in Tsukuba campus
    - Installation of a vertical-type collimator into LER
  - 2020 Spring run: 2020/1/16 (not fixed) ~ (7/1)
- The schedule of 2020~2021 are under discussion.
- Discussion about the strategy to increase the luminosity has just started.

The background of the slide features a central bright white point from which numerous thin, light-colored lines radiate outwards, creating a starburst or sunburst effect across the entire page.

Thank you for your attention.



# Backup